# IEC / IEEE 60802 - TSN IA profile



presented during meeting, off meeting, operated kick-off meeting, operated

# Scope and Status

Prepared by Günter Steindl (Siemens AG)

# Basic scope - PAR -



IEC / IEEE 60802 project authorization request (PAR):

http://www.ieee802.org/1/files/public/docs2018/60802-draft-PAR-0318-v01.pdf


- **2.1 Title:** Time-Sensitive Networking Profile for Industrial Automation
- **5.2 Scope:** This standard defines time-sensitive networking profiles for industrial automation. The profiles select features, options, configurations, defaults, **protocols and procedures of bridges, end stations, and LANs** to build **industrial automation networks**.
- **5.5 Need for the Project:** IEEE 802 standards address a very wide range of networking scenarios. Users and vendors of interoperable bridged time-sensitive networks for **industrial automation need guidelines for the selection and the use of IEEE 802 standards and features** in order to be able to deploy converged networks to simultaneously support operations technology traffic and other traffic.
- **5.6 Stakeholders for the Standard:** Developers, providers, vendors, and users of networking services and components for **industrial automation equipment**. These components may include bridges, end stations, network interface cards, and integrated circuits.

# **Basic scope**

#### **SIEMENS**

Ingenuity for life






# **Basic scope** - Timeline -



# IEC/IEEE 60802 Draft timeline



# Basic scope - meeting cadence -



IEC / IEEE 60802 meets every two month face to face.

Three plenary and three interim meetings somewhere in US, Canada, Europe or Asia.

Sync call can be scheduled by the chair/editor as needed, e.g. every week or bi-weekly!

All meetings are scheduled parallel to the IEEE interim or plenary meetings to allow IEEE802.1 experts joining the IEC/IEEE 60802 working group.

Next meeting:

Hiroshima from 14.01. – 18.01.

# **IEEE** standards

# - Bridges and End-Stations -

SIEMENS
Ingenuity for life

IEC / IEEE 60802 defines a standard selection

IEEE802.3-2018 - IEEE Standard for Ethernet

IEEE802.1Q-2018 - Bridges and Bridged Networks

IEEE802.1AB-2016 - Station and Media Access Control Connectivity Discovery

IEEE802.1AS-2019\* - Timing and Synchronization for Time-Sensitive Applications

and optional more, e.g.

IEEE802.1CB-2017 - Frame Replication and Elimination for Reliability

IEEE802.1X-2010 - Port-based Network Access Control

. . .

# Configuration

# - Bridges and End-Stations -



IEC / IEEE 60802 defines a selection of managed objects for the selected standards and the access to this managed objects

http://www.ieee802.org/3/ad\_hoc/ngrates/public/16\_01/zhuang\_ecdc\_01\_0116.pdf

Netconf or Restconf

for the access of the selected managed objects using YANG models

and optional


Simple Network Management Protocol (SNMP)

for the access of the selected managed objects using MIBs

### Requirements

- Principle of interoperation -





### **Requirements**

### - Layers -



Application (e.g. Communication and Application Profile, and Vendor Model)

Middleware (e.g. Fieldbus layer, OPC UA, ...)

Network Configuration (e.g. netconf, restconf, SNMP, ...)

Configuration using defined managed — objects

Stream Configuration and Establishment (e.g. RAP, restconf, ...)

Ethernet/TSN
(e.g. Synchronization, Neighborhood detection, bounded latency communication, ...)

Scope of Vendor / Customer

Scope of e.g. IEC 61158-x-y / IEC 61784-x-y Goals:

• Co-operation as 2<sup>nd</sup> level of interoperability

Scope of TSN-IA Profile Goals:

- Co-existence as 1<sup>st</sup> level of interoperability
- Common hardware requirements

#### - What needs to be covered -




http://www.ieee802.org/1/files/public/docs2018/60802-industrial-use-cases-0918-v13.pdf

IEC/IEEE 60802 working group decided to start with a use case definition to ensure a fitting definition for the TSN-IA profile.

Network access and Network/Bridge need to be covered by the profile.

Application is out of scope!

Thus, data rates from 10Mbit/s up to 100Gbit/s, as defined by IEEE802.3 are selectable together with all MAU Types supporting the required IEEE standards.



# - Topics -

Basic definition, e.g. structure of an industrial network or TSN domain definitions are covered.

Additional, the area of concern – who is responsible for what – is shown.


Interconnection between TSN domains using different options are added due to customer feedback.

Synchronization – IEEE802.1AS-2019 is a core standard for the TSN-IA profile – is covered.

# SIEMENS Ingenuity for life

2 -	<ul> <li>TSN·in·Ind</li> </ul>	ustrial-Automation <del>.</del>	9٩
2	2.1 → Interop	perability10	٥٩
		omain1′	
		eneral11	
		terconnection·of·TSN·Domains12	
		General	
		Bridges·(Layer·2)13	
		Routers·(Layer3)	
		Application Gateways (Layer7)15	

2.3	} → ;	Syn	chronization	······	15
_					
_			•		
				<del></del>	
_					: _



### - Topics -

Modes of operation as used in todays industrial automation systems need to be covered.

Thus, bidirectional connections, control loops and cyclic operation models are shown.


Control loops from some µs to ms are required together with cyclic data exchange of kBytes of real-time data.

Topologies like linear topology, star or ring are needed.

#### **SIEMENS**

Ingenuity for life

2.4 → Indu	ıstrial automation modes of operation	17
2.4.1 →	Industrial automation traffic types	17
2.4.1.1	→ General	17
2.4.1.2	→ Characterization of isochronous cyclic real-time and cyclic real-time	19
2.4.2 →	Bidirectional communication relations	20
2.4.3 →	Control·Loop·Basic·Model	21
2.4.4 →	Use·case·02:·Isochronous·Control·Loops·with·guaranteed·low·latency	229
2.4.4.1	→ Isochronous·cyclic·operation·model	25
2.4.4.2	→ Delay·requirements <del></del>	28
	Use·case·03:·Non-Isochronous·Control·Loops·with·bounded·latency	
2.4.5.1	→ Cyclic·operation·model <del></del>	30
2.4.5.2	→ Cyclic·traffic·pattern	31
2.4.6 →	Use·case·04:·Reduction·ratio·of·network·cycle <del>→</del>	32
	Use·case·05:·Drives·without·common·application·cycle	
	→ Background information	
	→ Controller·communication	
	→ Timing·Requirements	
2.4.8 →	Use·case·06: Drives·without·common·application·cycle·but·common·network·cycle.	35



### - Topics -

Industrial automation networks include today many different solutions.


TSN-IA profile shall not hinder any of this solutions – it shall support them.

This version of the TSN-IA profile will not support wireless, but its still needed for replacement of existing solutions.

High availability use cases or rather big domains need to be covered.



2.5 → Industrial automation networks <del></del> <del></del>	37¶
2.5.1 → Use·case·07:·Redundant·networks	37¶
2.5.2 → Use·case·08:·High·Availability	37¶
2.5.3 → Use·case·09:·Wireless	
2.5.4 → Use·case·10:·10°Mbit/s·end-stations·(Ethernet·sensors)	40¶
2.5.5 → Use case 11: Fieldbus gateway	40¶
2.5.6 → Use·case·12:·New·machine·with·brownfield·devices	41¶
2.5.7 → Use·case·13:·Mixed·link·speeds	42¶
2.5.8 → Use case 14: Multiple isochronous domains	
2.5.9 → Use case 15: Auto domain protection	45¶
2.5.10 → Use case 16: Vast number of connected stations	46¶
2.5.11 → Minimum·required·quantities	47¶
2.5.11.1 → A representative example for VLAN requirements	. <del></del> 47¶
2.5.11.2 → A·representative·example·for·data·flow·requirements	<del></del>
2.5.11.3 → A·representative·example·of·communication·use·cases	<del></del> 50¶
2.5.11.4 → "Fast" process applications	50¶
2.5.11.5 → Server·consolidation	51¶
2.5.11.6 → Direct·client·access	52¶
2.5.11.7 → Field·devices	52¶
2.5.12 → Bridge·Resources	53¶



# - Topics -


SIEMENS
Ingenuity for life

Industrial automation networks require dynamic extension of TSN domains together with the protection of a existing TSN domain.

These use cases are covered, too.

Process automation or DCS use cases are covered, too.

Additional use cases like network monitoring, digital twin or offline configuration are included.



2.	.6 → Industrial automation machines, production cells, production lines	. 56	Π
	2.6.1 → Use case 17: Machine to Machine/Controller to Controller (M2M/C2C)		
	Communication	. 56	Π
	2.6.2 → Use·case·18:·Pass-through·Traffic	. 58	Π
	2.6.3 → Use case 19: Modular machine assembly		Π
	2.6.4 → Use case 20: Tool changer		
	2.6.5 → Use·case·21: Dynamic·plugging·and·unplugging·of·machines·(subnets)	. 62	Π
	2.6.6 → Use·case·22: Energy·Saving	. 63	Π
	2.6.7 → Use·case·23:·Add·machine, production·cell·or·production·line	. 63	Π
	2.6.8 → Use case 24: Multiple applications in a station using the TSN-IA profile	. 64	
	2.6.9 → Use·case·25:·Functional·safety <del></del>	. 64	
	2.6.10 → Use·case·26:·Machine·cloning	. 65 <b>°</b>	
2.	.7 → DCS·Reconfiguration		
	2.7.1 → Challenges·of·DCS·Reconfiguration·Use·Cases		
	2.7.2 → Use·case·27:·DCS·Device·level·reconfiguration		
	2.7.3 → Use·case·28:·DCS·System·level·reconfiguration		
2.	.8 → Further·Industrial·Automation·Use·Cases		
	2.8.1 → Use·case·29:·Network·monitoring·and·diagnostics		
	2.8.2 → Use·case·30:·Security <del></del>		
	2.8.3 → Use·case·31:·Firmware·update		
	2.8.4 → Use·case·32:·Virtualization		
	2.8.5 → Use·case·33:·Offline·configuration		
	2.8.6 → Use·case·34:·Digital·twin		
	2.8.7 → Use case 35: Device replacement without engineering	. 729	
•	* 1	70.	~

# **Next steps**

# - Drafting the TSN-IA profile -



IEC / IEEE 60802 started drafting the TSN-IA profile spec in 11/2018.

Working version will be presented during the meeting in Hiroshima by the Editor.

All shown contributions – but not the spec draft – are public available together with the F2F meeting.

Liaisons or members are able to contribute to the IEC / IEEE 60802 working group!

#### Information

- How to participate -
- IEC participation is through National Committees
- IEEE 802 participation is on individual basis

- SIEMENS
  added for Ingenuity fit UPO
  added for Ingenuity fit UPO
  convenience,
  the
  convenienc
- Come to <u>face to face meetings</u> (registration required via <u>meeting page</u>)
- Attend <u>conference calls</u>
- Subscribe to the IEEE 802.1 email list
- Project web page: <a href="http://ieee802.org/1/tsn/iec-ieee-60802-tsn-profile-for-industrial-automation">http://ieee802.org/1/tsn/iec-ieee-60802-tsn-profile-for-industrial-automation</a>

# Thank you



# Questions?