Analysis of TSN for Industrial Automation based on Network Calculus

Jiayi Chang, Lihao Chen, Tongtong Wang, Xinyuan Wang Huawei Technologies





Purpose

- Share a paper from our team with the group
 - <<Analysis of TSN for Industrial Automation based on Network Calculus>>
 - Network calculus theory, industrial automation network modeling, and simulation results.
 - https://ieeexplore.ieee.org/document/8869053
- Discuss the idea of using network calculus to calculate the worst-case latency bound for industrial automation scenarios.
 - Vital for using asynchronous/non-time-based methods, e.g., SP with CBS or ATS.
 - What is the challenge? Where is the gap?

Network calculus theory

- Traffic characteristics / traffic constraints (TSpec in TSN)
- Device's capability (bandwidth, queuing and shaping, reservation)

 $\sim \operatorname{arrival} \operatorname{curve} \alpha(t) \xrightarrow{\operatorname{Network}} R^*(t)$ $\sim \operatorname{service} \operatorname{curve} \beta(t)$

Fig. 3. Two-port network model of a TSN relay node

$$R(s+t) - R(s) \le \alpha(t), \quad \forall \ s \ge 0, \ t \ge 0 \tag{1}$$

$$R^*(t) \ge R \otimes \beta(t) = \inf_{s \in \mathcal{S}} \{R(s) + \beta(t-s)\}, \quad \forall \ 0 \le s \le t \ (2)$$

→ arrival curve
→ The bound.
→ service curve





Fig. 4. Computation of backlog bound and delay bound.


Network calculus theory

CDT: Control Data Traffic



Industrial automation network modeling

• Topology, flows, and shapers.




FLOW DESCRIPTION

Flow path	Traffic Type	Forwarding	Priority
$\begin{array}{l} p_1: \ B, \ S_1, \ b_1 \\ p_2: \ B, \ S_1, \ b_1, \ b_2 \\ p_3: \ b_1, \ S_1, \ B \\ p_4: \ b_2, \ b_1, \ S_1, \ B \\ p_5: \ C, \ S_2, \ c_3 \\ p_6: \ C, \ S_2, \ c_3, \ c_4 \\ p_7: \ c_3, \ S_2, \ C \\ p_8: \ c_4, \ c_3, \ S_2, \ C \end{array}$	Isochronous	CDT (SP)	1
$\begin{array}{c} p_{9}: \ B, \ _{1}, \ S_{2}, \ C\\ p_{10}: \ C, \ S_{2}, \ S_{1}, \ B\\ p_{11}: \ A, \ S_{1}, \ B\\ p_{12}: \ B, \ S_{1}, \ A\\ p_{13}: \ A, \ S_{1}, \ S_{2}, \ C\\ p_{14}: \ C, \ S_{2}, \ S_{1}, \ A\\ p_{15}: \ C, \ S_{2}, \ c_{1}\\ p_{16}: \ C, \ S_{2}, \ c_{1}, \ c_{2}\\ p_{17}: \ c_{1}, \ S_{2}, \ C\\ p_{18}: \ c_{2}, \ c_{1}, \ S_{2}, \ C\\ p_{19}: \ b_{3}, \ b_{2}, \ b_{1}, \ S_{1}, \ B\\ p_{20}: \ B, \ S_{1}, \ b_{1}, \ b_{2}, \ b_{3} \end{array}$	Cyclic	SR Class A (CBS)	2
p ₂₁ : D ₁ , S ₂ , C p ₂₂ : D ₂ , S ₂ , S ₁ , A p ₂₃ : D ₃ , S ₂ , S ₁ , B	A/V	SR Class B (CBS)	3
p ₂₄ : A, S ₁ , B p ₂₅ : B, S ₁ , A p ₂₆ : A, S ₁ , S ₂ , C p ₂₇ : C, S ₂ , S ₁ , A	BE	BE (SP)	4

Fig. 5. Simulation topology

Most of the information used for modeling is referenced to past 60802 contributions and 60802 use case draft.

Industrial automation network modeling




FLOW DESCRIPTION

Flow path	Traffic Type	Forwarding	Priority	
$\begin{array}{l} p_1: \ B, \ S_1, \ b_1 \\ p_2: \ B, \ S_1, \ b_1, \ b_2 \\ p_3: \ b_1, \ S_1, \ B \\ p_4: \ b_2, \ b_1, \ S_1, \ B \\ p_5: \ C, \ S_2, \ c_3 \\ p_6: \ C, \ S_2, \ c_3, \ c_4 \\ p_7: \ c_3, \ S_2, \ C \\ p_8: \ c_4, \ c_3, \ S_2, \ C \end{array}$	Isochronous	CDT (SP)	1	Lmax=0.8kb T=2ms (cycle time) Lmax=0.8kb T=1ms (cycle time)
$\begin{array}{c} p_{9}: \ B, \ 1, \ S_{2}, \ C\\ p_{10}: \ C, \ S_{2}, \ S_{1}, \ B\\ p_{11}: \ A, \ S_{1}, \ B\\ p_{12}: \ B, \ S_{1}, \ A\\ p_{13}: \ A, \ S_{1}, \ S_{2}, \ C\\ p_{14}: \ C, \ S_{2}, \ S_{1}, \ A\\ p_{15}: \ C, \ S_{2}, \ c_{1}\\ p_{16}: \ C, \ S_{2}, \ c_{1}\\ p_{16}: \ C, \ S_{2}, \ c_{1}\\ p_{16}: \ C, \ S_{2}, \ C\\ p_{18}: \ c_{2}, \ c_{1}, \ S_{2}, \ C\\ p_{18}: \ c_{2}, \ c_{1}, \ S_{2}, \ C\\ p_{19}: \ b_{3}, \ b_{2}, \ b_{1}, \ S_{1}, \ B\\ p_{20}: \ B, \ S_{1}, \ b_{1}, \ b_{2}, \ b_{3}\\ \end{array}$		SR Class A (CBS =50%Bandwi		Lmax=0.8kb T=10ms
$\begin{array}{c} p_{21}: \ D_1, \ S_2, \ C\\ p_{22}: \ D_2, \ S_2, \ S_1, \ A\\ p_{23}: \ D_3, \ S_2, \ S_1, \ B \end{array}$	AN IdleSlopeB	<mark>SR Class B (CBS</mark> =25%Bandwi		Lmax=12kb r=1Mbps
$\begin{array}{c} p_{24}:A,S_1,B\\ p_{25}:B,S_1,A\\ p_{26}:A,S_1,S_2,C\\ p_{27}:C,S_2,S_1,A \end{array}$	BE	BE (SP)	4	Lmax=12kb

Most of the information used for modeling is referenced to past 60802 contributions and 60802 use case draft.


Simulation results

- The worst-case latency bound result with different bandwidth usage (i.e., different number of flows).
- Assuming that the latency requirement is 50%*T (cycle time) for all isochronous traffic, and is T for all cyclic traffic, then the result satisfies the requirement.
- Generally, the latency requirement could be tighter for isochronous cyclic real-time traffic and looser for cyclic real-time traffic.




Simulation results

- The worst-case latency bound result with different bandwidth usage (i.e., different number of flows).
- Assuming that the latency requirement is 50%*T (cycle time) for all isochronous traffic, and is T for all cyclic traffic, then the result satisfies the requirement.
- Generally, the latency requirement could be tighter for isochronous cyclic real-time traffic and looser for cyclic real-time traffic.
- If the latency requirement is 20%*T for isochronous traffic,,, oops!
- > What if there are even more flows, or more hops, or...



Simulation results

• Introducing offset to periodic traffic can get a better/tighter worst-case latency bound.



• Of course, there are many other ways to get a better/tighter worst-case latency bound.

Better: to make the actual worst-case latency less. Tighter: to make the calculated worst-case latency bound closer to the actual worst-case latency (reduce pessimism).

Discussion

- As in real industrial automation scenarios, the number of flows and nodes can be much larger than the model used in this paper, will network calculus still be able to provide a useful result of latency bound?
 - How to improve the NC math to get a tighter bound while the calculating complexity is acceptable?
 - How is the performance of ATS, or CBS/ATS combines with TAS?
 - How to optimize the parameter configuration of shapers?
 - Are there any better ways to describe a flow besides "b+rt"?

• Besides,

- Any other thoughts and concerns about using network calculus to calculate the worst-case latency bound for industrial automation scenarios?
- How to make the industrial automation network modeling closer to the real case?

Hope to get feedback from the group.

Thank you