Proposal of IR 10Mbps Communication Spec. to IEEE 802.11

Jointly Developed & Proposed by: SWCC,

ITT Cannon,

LTEL

Presented by: Masa Hirayama, LTEL

1

Proposal Outline:

- 1. Application to the current 802.11 MAC. 10Mbps and higher in the near future
- 2. Adjustment of the current PHY.

 Applicable on the higher transfer rate


Factors to be considered:

- 1. Precondition that the current MAC is to be applicable on 10-25-100Mbps.
- 2. Proposal that the current 4PPM-PHY or 16PPM-PHY is to be adjusted for DMI Modulation.

(DMI: Differential Mark Inversion)

3

Basic Connection Concept:



Performance of the new DMI Modem:

Error Rate: less than 10-10

Service Area: within the radius of 1m with


the spot reflection on the ceiling

Radiation Angle: ±10'


MAC & PHY: adjusted MAC & PHY

5

Setting of the Access Points on the ceiling:



IR Energy Calculation from the Access Point:



Pap=40(mW) x 24=960mW

So=25pi x 104=7.85 x 105(cm2)


if PD-square is 1cm2

Ppd=Pap/So=0.96/(7.85 x 105)=1.22 x 10-6(W)

 $(Pmin=700nW=0.7 \times 10-6W)$

,

Example of IR Communication with Wide Area Ceiling Reflection



Pmax=960mW

So=25pai x 104(cm2)

IR Energy Calculation: $S_8=(S_0/3-5x5x1.73/2 \times 104) \times 2$

 $=(26.18-21.65) \times 2 \times 104$

 $=9.06 \times 104(cm₂)$

Pss=(Pmax) x Ss/So

 $=960(mW) \times 0.115$

=110(mW)

if Pd square is 1cm2,

Ppd=0.11/So=1.4 x 10-7(W)

=140nW

9

Proposed Application on the current MAC:

Error Rate: more/less than 10-10

So

5m

2.5m

Service Area: within the radius of 5m with

wide area reflection on the ceiling

directly under the Access Point

Radiation Angle: ± 60 ' (with the hight of 2.5m)

MAC & PHY: applicable on the current MAC

and adjustment function to be added on the current PHY

for DMI module

Proposal of the adjusted PHY:


Current PHY with 4 and 16PPM:

Current modem circuit is fairly complicated, and the current PHY with 16PPM may not cope with the higher transfer rate imposing heavy burden on LED and optical circuit

Proposal of adjusted PHY for DMI Modulation: Basic application of Bi-Phase Modulation for easy DMI approach and better LED efficiency

11

Pulse Wave Comparison in IR Modulation:



Difference of LED Performance:

Current IR 4-16PPM Modulation:

In 10Mbps Data Transfer, the minimum Pulse Duty Ratio is 1/1 to 1/6 for 4PPM, and 1/1 to 1/30 for 16PPM

Proposed DMI Modulation:

In 10Mbps Data Transfer, the maximum and minimum pulse width are 50ns and 100ns;
Easy Synchlonized Extraction
Easy Optical Circuit with the Averaged Pulse Slower Response Capacity on LED

13

Expandability / Applicability in the Future:

Expandable Application to the higher Transfer Rate: DMI Modulation is easily applicable to 10, 25 to 100Mbps

Networking Communication:

Easily applicable to CSMA/CD and both Stable/Fixed and/or Portable/Mobil Communication

"Header" Construction for the DMI Modulation:

	P	F	A	ID	R	CRC	Ether net data	
P	: Preamble				24bi	t		
F:	Flag				8bit			
A:	Address	Address				8bit		
ID	D: Identification Address				8bit			
R:	Reserve				8bi	t		
CRC: Cyclic Redundancy Check					16bit			

15

Summary:

MAC: Establishing Compatibility with the current MAC

PHY: Adding Adjustment Function and Header on the current 4 & 16PPM PHY for DMI Modulation