Switched beam antennas in millimeter-wave band broadband wireless access networks

IEEE 802.16 Presentation Submission Template (Rev. 8.3)

Document Number:

IEEE S802 16-03/19

Date Submitted:

2003-07-16

Source:

J. Herrera, V. Polo, J. M. Martinez, Voice: +34 963879768 P. Sanchis, J. L. Corral, J. Marti Fax: +34 963877279

Universidad Politécnica de Valencia E-mail: jmarti@dcom.upv.es

Instituto ITACA, Edificio I-4 46022 - Valencia (SPAIN)

Venue:

IEEE 802.16 Session #26. WG meeting: Proposed New Concepts.

Base Document:

C802.16-03/09

http://ieee802.org/16/docs/03/C80216-03 09.pdf>

Purpose:

Contribution to the proposed new concepts in Session #26

Notice:

This document has been prepared to assist IEEE 802.16. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release:

The contributor grants a free, irrevocable license to the IEEE to incorporate material contained in this contribution, and any modifications thereof, in the creation of an IEEE Standards publication; to copyright in the IEEE's name any IEEE Standards publication even though it may include portions of this contribution; and at the IEEE's sole discretion to permit others to reproduce in whole or in part the resulting IEEE Standards publication. The contributor also acknowledges and accepts that this contribution may be made public by IEEE 802.16.

IEEE 802.16 Patent Policy:

The contributor is familiar with the IEEE 802.16 Patent Policy and Procedures http://ieee802.org/16/ipr/patents/policy.html, including the statement "IEEE standards may include the known use of patent(s), including patent applications, provided the IEEE receives assurance from the patent holder or applicant with respect to patents essential for compliance with both mandatory and optional portions of the standard." Early disclosure to the Working Group of patent information that might be relevant to the standard is essential to reduce the possibility for delays in the development process and increase the likelihood that the draft publication will be approved for publication. Please notify the Chair mailto:chair@wirelessman.org as early as possible, in written or electronic form, if patented technology (or technology under patent application) might be incorporated into a draft standard being developed within the IEEE 802.16 Working Group. The Chair will disclose this notification via the IEEE 802.16 web site http://ieee802.org/16/ipr/patents/notices.

Switched beam antennas in millimeter-wave band broadband wireless access networks

J. Herrera, V. Polo, J. M. Martinez, P. Sanchis, J. L. Corral, J. Marti

Universidad Politécnica de Valencia OBANET IST-2000-25390



More information at mailto:jmarti@dcom.upv.es http://ist-obanet.upv.es

OUTLINE

- Motivation
 - OBANET IST-2000-25390 project
- Objectives
- Switched-Beam Antenna scenario
- Performance improvement
 - Interference reduction
 - Multi-path reduction
 - Antenna Gain control
- Protocol adaptation to SBA scenario
- Remarks and conclusion

MOTIVATION

• Broadband Wireless Access (BWA) Networks

- High bit rates (>50 Mbps) obly to operate in the millimetre-wave band (targeted band 40-43 GHz)
- Frame duration 1 ms, channel size 28 MHz and M-QAM modulations formats target >50 Mbps
- Natural and artificial conditions drastically impair at mm-wave frequencies: rain, vegetation, man-made obstacles

- Dynamic antenna gain and coverage area
- Reduced multi-path and interferences
- Higher spectral efficiency and SDMA

Smart Antennas at 40 GHz?

MOTIVATION

Smart Antennas at 40 GHz

- Adaptive antennas: DSP and RF/IF
 - Very high speed DSPs (not yet available)
 - Beam-squint (radiation pattern depends on frequency)
 - High speed switches required for beam-switching.
 - Bulky hardware is required

Proposed approach

- Switched-Beam Antennas (SBA)
- Simplified architectures: optical beamforming, Butler matrix
 - however, the proposed strategies are technology-independent
- True-Time Delay is achieved no beam-squint
- Ultra-fast switching times up to nanoseconds

OBJECTIVES

• SBA is the simplest smart-antenna technology at 40 GHz suited as first implementation

OBJECTIVE 1: To demonstrate the benefits of introducing SBA in BWA networks

• However, BWA protocols must be adapted to introduce SBA → overhead


OBJECTIVE 2: To propose a adaptation to introduce SBA scenario in the BWA protocols

OBJECTIVE 3: To introduce an strategy to reduce the overhead

SWITCHED BEAM ANTENNA SCENARIO

• Scenario defined fitting IEEE/ETSI draft standards (2001) $\Theta_{\text{contor}} = 90^{\circ}$ Micro-sector

- Operation frequency: 42.7 GHz
- IEEE/ETSI fixed frame format
- TDD and TDM/TDMA operation mode



SBA control and performance evaluated

- Interference and multipath reduction
- Antenna gain control
- Adaptation of BWA protocols reducing overhead
- pointing directions and beamwidths

PERFORMANCE OPTIMISATION


Interference reduction

— Outage probability as a function of the required C/I for different SBA configurations (SLL^{BS} =20 dB, SLL^{SS} =15 dB and $\Delta \phi^{SS}_{-3dB}$ =3°) in the downlink direction

f2h	f1v	flv	f2h	f2h	flv	flv	f2h
flh	f2v	f2v	flh	flh	f2v	f2v	flh
flh	f2v	f2v	flh	flh	f2v	f2v	flh
f2h	flv	flv	f2h	f2h	flv	flv	f2h
f2h	flv	flv	f2h	f2h	flv	flv	f2h
flh	f2v	f2v	flh	flh	f2v	f2v	flh
flh	f2v	f2v	flh	flh	f2v	f2v	flh
f2h	flv	flv	f2h	f2h	flv	flv	f2h

Cellular reuse pattern:

- 2 Frequencies
- 2 Polarisations



PERFORMANCE IMPROVEMENT


Interference reduction

— C/I required to obtain an outage probability of 1% as a function of the radius of the coverage area for different SBA configurations

Higher order modulation formats can be employed in a larger coverage area

$\Delta \phi_{ ext{-3dB}}$	CA		
90°	1200 m		
22.5°	2000 m		
11.25°	>2500 m		

For a BER=10⁻¹¹ at **16-QAM** (required C/I 21 dB)




Overall capacity enhancement

PERFORMANCE IMPROVEMENT

Multipath reduction


- BER improvement
- Temporal dispersion of the channel is reduced
- Easier equalisation simplified wireless modem design



PERFORMANCE IMPROVEMENT

Dynamic antenna control

- Useful to counteract temporary channel impairments
- Less interferences than Power Control techniques
- Sector reconfiguration possible



Availability and Flexibility improvement


PROTOCOL ADAPTATION

Broadcast and contention access

- Clearly unfeasible in the SBA scenario
- Solution: replication of broadcast and content intervals in each beam
- Introduces overhead, specially the broadcast of control information

Adaptation to the SBA scenario

- Slot-based beam switching approach preferred
- Replication minimization using location




PROTOCOL ADAPTATION


Map minimisation

- Local DL_MAP and UL_MAP to each beam pointing direction
- Location may be easily obtained in the SS registration
- Only SS present in each beam are mapped in the local DL_MAP
- Only SS present in each beam are allocated in the local UL_MAP

— Different preamble sequences



DL_MAP and **UL_MAP** format



Low impact for high loads

REMARKS AND CONCLUSION

- Several strategies making use of beam-forming and fast beam-switching capabilities are possible with adaptive beam-formed BS antennas
- The use of such strategies lead mainly to:
 - interference reduction, capacity improvement
 - better quality of service
 - improved system flexibility
- These benefits are of key importance for next generation multimedia fixed broadband wireless access networks

REMARKS AND CONCLUSION

- A strategy to adapt the SBA scenario and to minimize the protocol overhead introduced in BWA protocols has been proposed:
 - slot-based beam-switching
 - minimization using location
 - efficient for high-loads

Thanks for your attention

More information at http://ist-obanet.upv.es