2 Contributor group

This document is created by Don Pannell. If you wish to be a Contributor to this document, whether or not you wish your name to be listed below, please contact Don at donald.pannell@nxp.com. Feedback is welcome! Please e-mail corrections/issues with suggested text.

Dorr, Josef <josef.dorr@siemens.com> - for the source format of this document Pannell, Don <donald.pannell@nxp.com> - this document creator Potts, Mike <mike.potts@gm.com> - for Use Case presentations Zinner, Helge <helge.zinner@conti.de> - for Use Case presentation

Abstract

This document summarizes use cases relevant to Automotive Time Sensitive Networking (TSN), along with their associated requirements. It will be used by the IEEE P802.1DG editor to create the standard. The IEEE P802.1DG project's title is: "TSN Profile for Automotive In-Vehicle Ethernet Communications."

The enclosed use cases are intended to guide the specification process: WHAT shall be part of the standard and WHY. Then the content of IEEE P802.1DG standard specifies the HOW to achieve these use cases.

Some use cases are on a system level of an automotive system, even if the scope of IEEE P802.1DG does not cover the overall system level. The IEEE P802.1DG should enable or at least do not prevent the features described in this use case document. Example use cases that are currently outside the scope of the P802.1DG standard are those using wireless interfaces, but these uses clearly impact the "Ethernet Communications" use in the vehicle.

This document is intended an aide to the formation of the IEEE P802.1DG standard.

23 **Log**

V0.1 2019-May-20 First version – to show structure and flow only.

V0.2 2019-May-20 First version text with Industrial text showed in Black & the new Automotive text showed in Green so that the new Automotive text is easier to see.

_

-

_

24 25

Use Cases For: IEEE P802.1DG Page 2 of 79

Content

26

27	Contributor group	
28	Abstract	
29	Log	
30	Content	
31	Figures	
32	Tables	
33	1 Definitions and Terms	7
34	1.1 Definitions	7
35	1.2 IEEE 802.1 Terms	8
36	2 TSN in Automotive	9
37	2.1 Interoperability	9
38	2.2 TSN Domain	10
39	2.2.1 General	10
40	2.2.2 Interconnection of TSN Domains	
41	2.2.2.1 General	
42	2.2.2.2 Bridges (Layer 2)	
43	2.2.2.3 Routers (Layer3)	
44	2.2.2.4 Application Gateways (Layer7)	
45	2.3 Synchronization	
46	2.3.1 General	
47	2.3.2 Universal Time Synchronization	
48	2.3.3 Working Clock Synchronization	
1 0 49	2.3.4 Sequence of events	
50	2.4 Redundancy	
50 51	2.5 Security	
52	2.6 Automotive traffic types	
52 53	2.6.1 General	
53 54	2.6.2 Bidirectional communication relations	
5 4 55	2.6.3 Control Loop Basic Model	
56	3 Automotive modes of operation – the Use Cases	
50 57		
58	3.1.1 Traditional or Central Gateway Model	
59		
60	3.2 Use case 02: Isochronous Control Loops with guaranteed low latency	
31	3.2.1.1 Isochronous cyclic operation model	
62	3.2.1.2 Delay requirements	
33	3.3 Use case 03: Non-Isochronous Control Loops with bounded latency	
64 -	3.3.1.1 Cyclic operation model	
35	3.3.1.2 Cyclic traffic pattern	
66	3.4 Use case 04: Reduction ratio of network cycle	
67	3.5 Use case 05: Drives without common application cycle	
86	3.5.1.1 Background information	
69	3.5.1.2 Controller communication	
70	3.5.1.3 Timing Requirements	
71	3.6 Use case 06: Drives without common application cycle but common network cycle	38
72	3.7 Industrial automation networks	
73	3.7.1 Use case 07: Redundant networks	
74	3.7.2 Use case 08: High Availability	
75	3.7.3 Use case 09: Wireless	41

77 3.7.6 Use case 12: New machine with brownfield devices	76	3.7.4	Use case 10: 10 Mbit/s end-stations (Ethernet sensors)	43
79 3.7.7 Use case 13: Mixed link speeds. .46 80 3.7.8 Use case 14: Multiple isochronous domains. .47 81 3.7.9 Use case 16: Vast number of connected stations. .48 82 3.7.10 Use case 16: Vast number of connected stations. .49 83 3.7.11.1 A representative example for VLAN requirements. .50 84 3.7.11.2 A representative example for data flow requirements. .53 85 3.7.11.3 A representative example of communication use cases. .54 86 3.7.11.5 A representative example of communication use cases. .54 87 3.7.11.5 Server consolidation. .55 89 3.7.11.5 Server consolidation. .55 89 3.7.11.6 Direct client access. .56 90 3.7.11.7 Field devices. .57 91 3.7.12 Bridge Resources. .57 91 3.7.12 Bridge Resources. .57 92 3.8 Industrial automation machines, production cells, production	77	3.7.5		
80 3.7.8 Use case 15: Multiple isochronous domains 47 81 3.7.9 Use case 15: Auto domain protection 48 82 3.7.10 Use case 16: Vast number of connected stations 49 83 3.7.11 Minimum required quantities 50 84 3.7.11.1 A representative example for VLAN requirements 50 85 3.7.11.2 A representative example of communication use cases 54 86 3.7.11.3 A representative example of communication use cases 54 87 3.7.11.4 "Fast' process applications 55 88 3.7.11.5 Server consolidation 55 89 3.7.11.6 Direct client access 56 90 3.7.11.7 Field devices 57 91 3.7.12 Bridge Resources 57 92 3.8 Industrial automation machines, production cells, production lines 60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2WC2C) 57 94 Communication 60	78	3.7.6	Use case 12: New machine with brownfield devices	45
81 3.7.9 Use case 16: Auto domain protection .48 82 3.7.10 Use case 16: Vast number of connected stations .49 83 3.7.11.1 Minimum required quantities .50 84 3.7.11.2 A representative example for VLAN requirements .50 85 3.7.11.2 A representative example for data flow requirements .53 86 3.7.11.4 "Fast" process applications .54 87 3.7.11.4 "Fast" process applications .54 88 3.7.11.5 Server consolidation .55 89 3.7.11.7 Field devices .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) .60 94 Communication .60 .60 93 3.8.1 Use case 18: Pass-through Traffic .62	79	3.7.7	Use case 13: Mixed link speeds	46
82 3.7.10 Use case 16: Vast number of connected stations .49 83 3.7.11 Minimum required quantities .50 84 3.7.11.2 A representative example for VLAN requirements .50 85 3.7.11.2 A representative example for data flow requirements .53 86 3.7.11.3 A representative example of communication use cases .54 87 3.7.11.5 Server consolidation .54 88 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 20: Tool changer .65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 99	80	3.7.8	Use case 14: Multiple isochronous domains	47
83 3.7.11 Minimum required quantities 50 84 3.7.11.1 A representative example for VLAN requirements 50 85 3.7.11.2 A representative example for data flow requirements 53 86 3.7.11.3 A representative example of communication use cases .54 87 3.7.11.4 "Fast" process applications .55 88 3.7.11.6 Direct client access .56 89 3.7.11.7 Field devices .57 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 98 3.8.5 Use case 22: Energy Saving .67	81	3.7.9		
84 3.7.11.1 A representative example for VLAN requirements .50 85 3.7.11.2 A representative example for data flow requirements .53 86 3.7.11.3 A representative example of communication use cases .54 87 3.7.11.4 "Fast" process applications .54 88 3.7.11.5 Server consolidation .55 89 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 19: Modular machine assembly .64 97 3.8.4 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets	82	3.7.10		
85 3.7.11.2 A representative example for data flow requirements .53 86 3.7.11.3 A representative example of communication use cases .54 87 3.7.11.4 "Fast" process applications .54 88 3.7.11.5 Server consolidation .55 89 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 29: Modular machine assembly .64 97 3.8.4 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 98 3.8.5 Use case 22: Energy Saving .67 100 3.8.7 Use case 23: Add machine, production cell or production line .67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile .68 102 3.8.9 Use case 26: Machine cl				
86 3.7.11.3 A representative example of communication use cases. .54 87 3.7.11.4 "Fast" process applications. .54 88 3.7.11.5 Server consolidation. .55 89 3.7.11.6 Direct client access. .56 90 3.7.11.7 Field devices. .57 91 3.7.12 Bridge Resources. .57 92 3.8 Industrial automation machines, production cells, production lines. .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) .60 94 Communication. .60 95 3.8.2 Use case 18: Pass-through Traffic. .62 96 3.8.3 Use case 20: Tool changer. .65 98 3.8.4 Use case 20: Tool changer. .65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets). .66 99 3.8.6 Use case 22: Energy Saving. .67 100 3.8.7 Use case 23: Add machine, production cell or production line. .67 101 3.8.8 Use case 25: Functional safety. <t< td=""><td></td><td></td><td></td><td></td></t<>				
87 3.7.11.4 "Fast" process applications .54 88 3.7.11.5 Server consolidation .55 89 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 19: Modular machine assembly .64 97 3.8.4 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 98 3.8.5 Use case 22: Energy Saving .67 100 3.8.7 Use case 23: Add machine, production cell or production line .67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile .68 102 3.8.9 Use case 25: Functional safety .69		_		
88 3.7.11.5 Server consolidation .55 89 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) .60 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 19: Modular machine assembly .64 97 3.8.4 Use case 20: Tool changer .65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 99 3.8.6 Use case 22: Energy Saving .67 100 3.8.7 Use case 23: Add machine, production cell or production line .67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile .68 102 3.8.9 Use case 25: Functional safety .69 3.8.1 Lye case 26: Machine cloning .6				
89 3.7.11.6 Direct client access .56 90 3.7.11.7 Field devices .57 91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) .60 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 20: Tool changer .62 97 3.8.4 Use case 20: Tool changer .65 98 3.8.5 Use case 22: Energy Saving .67 100 3.8.7 Use case 23: Add machine, production cell or production line .67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile .68 102 3.8.9 Use case 25: Functional safety .69 3.8.10 Use case 26: Machine cloning .69 3.9.1 Challenges of DCS Reconfiguration .70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases .70 107 </td <td>-</td> <td></td> <td></td> <td></td>	-			
90 3.7.11.7 Field devices				
91 3.7.12 Bridge Resources .57 92 3.8 Industrial automation machines, production cells, production lines .60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication .60 95 3.8.2 Use case 18: Pass-through Traffic .62 96 3.8.3 Use case 19: Modular machine assembly .64 97 3.8.4 Use case 20: Tool changer .65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) .66 99 3.8.6 Use case 22: Energy Saving .67 100 3.8.7 Use case 23: Add machine, production cell or production line .67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile .68 102 3.8.9 Use case 25: Functional safety .69 103 3.8.10 Use case 26: Machine cloning .69 104 3.9 DCS Reconfiguration .70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases .70 106 3.9.2 Use case 27: DCS				
92 3.8 Industrial automation machines, production cells, production lines 60 93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication 60 95 3.8.2 Use case 18: Pass-through Traffic 62 96 3.8.3 Use case 19: Modular machine assembly 64 97 3.8.4 Use case 20: Tool changer 65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) 66 99 3.8.6 Use case 22: Energy Saving 67 100 3.8.7 Use case 23: Add machine, production cell or production line 67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile 68 102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 71 107 3.9.3 U		_		
93 3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) 94 Communication				
94 Communication				60
95 3.8.2 Use case 18: Pass-through Traffic				
96 3.8.3 Use case 19: Modular machine assembly 64 97 3.8.4 Use case 20: Tool changer 65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) 66 99 3.8.6 Use case 22: Energy Saving 67 100 3.8.7 Use case 23: Add machine, production cell or production line 67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile 68 102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10.1 Use case 29: Network monitoring and diagnostics 72 109 3.10.2 Use case 30: Security 73 111 3.10.2 Use case 33: Virtualization 74 112 3.10.4				
97 3.8.4 Use case 20: Tool changer 65 98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets) 66 99 3.8.6 Use case 22: Energy Saving 67 100 3.8.7 Use case 23: Add machine, production cell or production line 67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile 68 102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 30: Security 73 110 3.10.2 Use case 31: Firmware update 73 112 3.10.4 Use case 33: Offline configuration 74 13 3.10.5 U				
98 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets)				
99 3.8.6 Use case 22: Energy Saving	-			
100 3.8.7 Use case 23: Add machine, production cell or production line 67 101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile 68 102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 35: Device replacement without engineering 76 115 Abbrevia				
101 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile 68 102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 16 Abbreviations 78 </td <td></td> <td></td> <td></td> <td></td>				
102 3.8.9 Use case 25: Functional safety 69 103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78				
103 3.8.10 Use case 26: Machine cloning 69 104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78				
104 3.9 DCS Reconfiguration 70 105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78			·	
105 3.9.1 Challenges of DCS Reconfiguration Use Cases 70 106 3.9.2 Use case 27: DCS Device level reconfiguration 70 107 3.9.3 Use case 28: DCS System level reconfiguration 71 108 3.10 Further Industrial Automation Use Cases 72 109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78				
106 3.9.2 Use case 27: DCS Device level reconfiguration .70 107 3.9.3 Use case 28: DCS System level reconfiguration .71 108 3.10 Further Industrial Automation Use Cases .72 109 3.10.1 Use case 29: Network monitoring and diagnostics .72 110 3.10.2 Use case 30: Security .73 111 3.10.3 Use case 31: Firmware update .73 112 3.10.4 Use case 32: Virtualization .74 113 3.10.5 Use case 33: Offline configuration .75 114 3.10.6 Use case 34: Digital twin .76 115 3.10.7 Use case 35: Device replacement without engineering .76 116 Abbreviations .78 117 Literature and related Contributions .78				
107 3.9.3 Use case 28: DCS System level reconfiguration .71 108 3.10 Further Industrial Automation Use Cases .72 109 3.10.1 Use case 29: Network monitoring and diagnostics .72 110 3.10.2 Use case 30: Security .73 111 3.10.3 Use case 31: Firmware update .73 112 3.10.4 Use case 32: Virtualization .74 113 3.10.5 Use case 33: Offline configuration .75 114 3.10.6 Use case 34: Digital twin .76 115 3.10.7 Use case 35: Device replacement without engineering .76 116 Abbreviations .78 117 Literature and related Contributions .78				
108 3.10 Further Industrial Automation Use Cases .72 109 3.10.1 Use case 29: Network monitoring and diagnostics .72 110 3.10.2 Use case 30: Security .73 111 3.10.3 Use case 31: Firmware update .73 112 3.10.4 Use case 32: Virtualization .74 113 3.10.5 Use case 33: Offline configuration .75 114 3.10.6 Use case 34: Digital twin .76 115 3.10.7 Use case 35: Device replacement without engineering .76 116 Abbreviations .78 117 Literature and related Contributions .78				
109 3.10.1 Use case 29: Network monitoring and diagnostics 72 110 3.10.2 Use case 30: Security 73 111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78				
110 3.10.2 Use case 30: Security				
111 3.10.3 Use case 31: Firmware update 73 112 3.10.4 Use case 32: Virtualization 74 113 3.10.5 Use case 33: Offline configuration 75 114 3.10.6 Use case 34: Digital twin 76 115 3.10.7 Use case 35: Device replacement without engineering 76 116 Abbreviations 78 117 Literature and related Contributions 78				
112 3.10.4 Use case 32: Virtualization .74 113 3.10.5 Use case 33: Offline configuration .75 114 3.10.6 Use case 34: Digital twin .76 115 3.10.7 Use case 35: Device replacement without engineering .76 116 Abbreviations .78 117 Literature and related Contributions .78				
113 3.10.5 Use case 33: Offline configuration .75 114 3.10.6 Use case 34: Digital twin .76 115 3.10.7 Use case 35: Device replacement without engineering .76 116 Abbreviations .78 117 Literature and related Contributions .78			·	
1143.10.6Use case 34: Digital twin.761153.10.7Use case 35: Device replacement without engineering.76116Abbreviations.78117Literature and related Contributions.78				
115 3.10.7 Use case 35: Device replacement without engineering				
116 Abbreviations				
117 Literature and related Contributions78				
	118			

Use Cases For: IEEE P802.1DG Page 4 of 79

124	Figures

125	Figure 1 – Principle of interoperation	9
126	Figure 2 – Scope of work	.10
127	Figure 3 – Different Types of Domains	.11
128	Figure 4 – Three TSN domains connected by Bridges	.12
129	Figure 5 – Three TSN domains connected by Routers	
130	Figure 6 – Gateways with two TSN domains and an attached Fieldbus	
131	Figure 7 – plant wide time synchronization	
132	Figure 8 – line/cell/machine wide working clock synchronization overlapping with a universal time	
133	domain	
134	Figure 9 – Bidirectional Communication	
135	Figure 10 – Principle data flow of control loop	
136	Figure 11 – Examples of Traditional or Central Gateway Automotive Networks	
137	Figure 12 – Examples of Domain Automotive Networks	
138	Figure 13 – network cycle and isochronous application (Basic model)	
139	Figure 14 – Multiple concurrent isochronous control loops (Extended model)	
140	Figure 15 – Variation 1: two cycle timing model	
141	Figure 16 – Variation 2: two cycle timing model - shifted by 180°	
142	Figure 17 – Variation 3: three cycle timing model	
143	Figure 18 – Variation 4: one cycle timing model	
144	Figure 19 – Variation 5: one cycle timing model – changed sequence	
145	Figure 20 – Variation 6: further optimizations	
146	Figure 21 – isochronous cyclic operation model	
147	Figure 22 – delay measurement reference points	
148	Figure 23 – network cycle and non-isochronous application (Basic model)	
149	Figure 24 – cyclic operation model	
150	Figure 25 – network cycle and application cycle	
151	Figure 26 – isochronous drive synchronization	
152	Figure 27 – network with different application cycles	.37
153	Figure 28 – Multivendor Motion – Controller communication	
154	Figure 29 – Multivendor Motion – Timing Requirements	.38
155	Figure 30 – different application cycles but common network cycle	.39
156	Figure 31 – ring topology	.40
157	Figure 32 – connection of rings	.40
158	Figure 33 – example topology for tunnel control	
159	Figure 34 – HMI wireless connected using cyclic real-time	.42
160	Figure 35 – Remote IO wireless connected using cyclic real-time	
161	Figure 36 – Ring segment wireless connected for media redundancy	
162	Figure 37 – Ethernet sensors	
163	Figure 38 – fieldbus gateways	
164	Figure 39 – Embedded non TSN communication	
165	Figure 40 – New machine with brownfield devices	
166	Figure 41 – Add TSN machine to brownfield machine	
167	Figure 42 – mixed link speeds	
168	Figure 43 – mixed link speeds without topology guideline	
169	Figure 44 – multiple isochronous domains	
170	Figure 45 – multiple isochronous domains - coupled	
171	Figure 46 – Auto domain protection	
172	Figure 47 – Topologies, trees and VLANs	
173	Figure 48 – Logical communication concept for fast process applications	.55

174	Figure 49 – Server consolidated logical connectivity	55
175	Figure 50 – Clients logical connectivity view	
176	Figure 51 – Field devices with 10Mbit/s	
177	Figure 52 – M2M/C2C between TSN domains	
178	Figure 53 – M2M with supervisory PLC	
179	Figure 54 – M2M with four machines	
180	Figure 55 – M2M with diagnostics/monitoring PC	
181	Figure 56 – pass-through one machine	
182	Figure 57 – pass-through one machine and production cell	
183	Figure 58 – pass-through two machines	63
184	Figure 59 – machine with diagnostics / monitoring PC	63
185	Figure 60 – modular bread-machine	
186	Figure 61 – modular advertisement feeder	65
187	Figure 62 – tool changer	65
188	Figure 63 – AGV plug and unplug	66
189	Figure 64 – energy saving	67
190	Figure 65 – add machine	68
191	Figure 66 – two applications	68
192	Figure 67 – Functional safety with cyclic real-time	69
193	Figure 68 – Machine internal communication with isolated logical infrastructure	70
194	Figure 69 – Device level reconfiguration use cases	71
195	Figure 70 – System level reconfiguration use cases	72
196	Figure 71 – Ethernet interconnect with VM based vBridge	74
197	Figure 72 – Ethernet interconnect with PCIe connected Bridge	75
198		
199		
200		
201		
202	Tables	
203	Table 1 – Industrial automation traffic types summary	
204	Table 2 – isochronous cyclic real-time and cyclic real-time traffic type properties	
205	Table 3 – Application types	
206	Table 4 – isochronous traffic pattern properties	29
207	Table 5 – Expected PHY delays	
208	Table 6 – Expected MAC delays	
209	Table 7 – Expected Ethernet Bridge delays	
210	Table 8 – cyclic traffic pattern properties	
211	Table 9 – Link speeds	
212	Table 10 – Expected number of stream FDB entries	
213	Table 11 – Expected number of non-stream FDB entries	
214	Table 12 – Neighborhood for hashed entries	
215	Table 13 – MinimumFrameMemory for 100 Mbit/s (50%@1 ms)	
216	Table 14 – MinimumFrameMemory for 1 Gbit/s (20%@1 ms)	
217	Table 15 – MinimumFrameMemory for 2,5 Gbit/s (10%@1 ms)	
218	Table 16 – MinimumFrameMemory for 10 Gbit/s (5%@1 ms)	59

219 1 Definitions and Terms

220 <<creator's note: The Definitions & Terms listed below are some Automotive specific definitions

that have been added along with examples as listed in the Industrial Use Case document. This list

will be updated & added to as needed. The intended edits for the next revision are marked.

Suggestions of what should be kept or deleted is requested.>>

223224

225 1.1 Definitions

ADAS Adaptive Driver Assistance System – needed for autonomous driving

ADAS Level Autonomous driving capability levels as defined by the Society of

Automotive Engineers (SAE)

Level 0: Driver controls it all, to Level 5: Fully autonomous in all environments/scenarios (no steering wheel necessary). See:

https://www.techrepublic.com/article/autonomous-driving-levels-0-to-5-

understanding-the-differences/

CAN(-FD) Controller Area Network - a vehicle bus standard, '-FD' stands for the

Flexible Data-rate extension

DC Domain Controller

ECU Electronic Control Unit

LIN Local Interconnect Network - a vehicle bus standard

OEM Original Equipment Manufacturer – In Automotive: The Car Maker

Tier 1 In Automotive: typically, a subsystem/ECU supplier

Tier 2 In Automotive: typically, a silicon supplier

Reconfiguration Any intentional modification of the system structure or of the device-

level content, including updates of any type

Operational state Normal state of function of a unit

Maintenance state Planned suspension or partial suspension of the normal state of

function of a unit

Stopped state Full non-productive mode of a unit

Convergent network

concept

All LAN devices (wired or wireless) can exchange data over a common

infrastructure, within defined QoS parameters

<<creator's note: TSN over wireless media is outside the scope of IEEE P802.1DG (it's title specifically states Ethernet Communications), the include of wireless devices in use cases may be needed to show the system level

need.>>

Use Cases For: IEEE P802.1DG Page 7 of 79

Device End station, bridged end station, bridge, access point

Transmission selection

algorithms

A set of algorithms for traffic selection which include Strict Priority, the Credit-based shaper and Enhanced Transmission Selection.¹⁾

Preemption The suspension of the transmission of a preemptable frame to allow

one or more express frames to be transmitted before transmission of

the preemptable frame is resumed.1)

Enhancements for scheduled traffic

A Bridge or end station may support enhancements that allow transmission from each queue to be scheduled relative to a known

timescale.1)

Time-Sensitive Stream A stream of traffic, transmitted from a single source station, destined

for one or more destination stations, where the traffic is sensitive to timely delivery, and, requires transmission latency to be bounded.¹⁾

TSN domain A quantity of commonly managed devices;

A set of devices, their Ports, and the attached individual LANs that transmit Time-Sensitive Streams using TSN standards which include Transmission Selection Algorithms, Preemption, Time Synchronization and Enhancements for Scheduled Traffic and that share a common

management mechanism.

It is an administrative decision to group these devices (see 2.2).

universal time domain working clock domain

gPTP domain used for the synchronization of universal time

ock domain gPTP domain used for the synchronization of a working clock

isochronous domain

Devices of a common working clock domain with a common setup for

the isochronous cyclic real-time traffic type

cyclic real-time domain

Devices with a common setup for the cyclic real-time traffic type - even from different working clock domains or synchronized to a local

timescale

Network cycle Transfer time including safety margin, and application time including

safety margin (see Figure 13); values are specific to a TSN domain and specify a repetitive behavior of the network interfaces belonging to

that TSN domain;

Stream forwarding Forwarding of stream data along the stream path including TSN

domain boundary crossings

1.2 IEEE 802.1 Terms

Priority regeneration See IEEE 802.1Q-2018 clause 6.9.4 Regenerating priority

Ingress rate limiting See IEEE 802.1Q-2018 clause 8.6.5 Flow classification and metering

¹ taken from 802.1Q-2018

Use Cases For: IEEE P802.1DG Page 8 of 79

227

226

2 TSN in Automotive

228

233

239

240

241

250

229 <<creator's note: The Industrial Use Case document used this section to describe Cyber-Physical Systems. I</p>

- propose this section can be a brief overview of non-Ethernet in-vehicle networks and where & why
- 231 Ethernet came into the Automotive picture. If people feel this is not needed, this section would just be an
- 232 overview of what comes below.>>

2.1 Interoperability

- 234 <<creator's note: What parts of this section from the Industrial Use Case document are applicable to</p>
- 235 Automotive? Clearly there is a desire for interoperability of devices. But Automotive is historically static in
- 236 its network construction, even if the flows of streams are altered by firmware updates.>>
- Interoperability may be achieved on different levels. Figure 1 and Figure 2 show three areas, which need to be covered:
 - network configuration (managed objects according to IEEE definitions), and
 - stream configuration and establishment, and
 - application configuration.
- The three areas mutually affect each other (see Figure 1).
- Application configuration is not expected to be part of the profile, but the two other areas are.
- The selection made by the TSN-IA profile covers IEEE 802 defined layer 2 and the selected protocols to configure layer 2.
- Applications make use of upper layers as well, but these are out of scope for the profile.
- 247 Stream establishment is initiated by applications to allow data exchange between applications. The
- 248 applications are the source of requirements, which shall be fulfilled by network configuration and
- 249 stream configuration and establishment.




Figure 1 – Principle of interoperation

251252253

Use Cases For: IEEE P802.1DG Page 9 of 79




Figure 2 - Scope of work

2.2 TSN Domain

<<creator's note: What parts of this section from the Industrial Use Case document are applicable to Automotive? Is this concept needed for Automotive?>>

2.2.1 General

254 255

256

257

258

259

260

261

262

264

265

266

267268

269

270

A <u>TSN domain</u> is defined as a quantity of commonly managed industrial automation devices; it is an administrative decision to group these devices.

263 TSN Domain Characteristics:

- One or more TSN Domains may exist within a single layer 2 broadcast domain.
- A TSN Domain may not be shared among multiple layer 2 broadcast domains.
- Multiple TSN Domains may share a common universal time domain.
- Two adjacent TSN Domains may implement the same requirements but stay separate.
- Multiple TSN domains will often be implemented in one bridge (see 2.2.2.2).
- Multiple TSN domains will often be implemented in one router (see 2.2.2.3).
- Multiple TSN domains will often be implemented in one gateway (see 2.2.2.4).


Typically machines/functional units constitute separate TSN domains. Production cells and lines may be set up as TSN domains as well. Devices may be members of multiple TSN domains in parallel.

Figure 3 shows two example TSN domains within a common broadcast domain and a common universal time domain. TSN domain 1 is a pure cyclic real-time domain, whereas TSN domain 2

additionally includes three overlapping isochronous domains.

Use Cases For: IEEE P802.1DG Page 10 of 79

277



278279


Figure 3 - Different Types of Domains

- 280 Interconnections between TSN domains are described in 2.2.2 and 3.8.1.
- 281 2.2.2 Interconnection of TSN Domains
- 283 TSN domains may be connected via
- 284 Bridges (Layer 2), or
- 285 Routers (Layer 3), or
- Application Gateways (Layer 7).
- 287 Wireless Access Points or 5G Base Stations may be used to connect TSN domains, too.

Use Cases For: IEEE P802.1DG Page 11 of 79

- When a Bridge is member of multiple TSN domains, one bridge port must only be a member of a single TSN domain.
- 291 Figure 4 provides an example of two Bridges, which are members of two TSN domains each.
- 292 Bridge B1 provides ports and connectivity in TSN domain Production Cell 1 and in TSN domain
- 293 Machine 1, Bridge B2 for Production Line 1 and Production Cell 1.

294



295 296

297

298

299

300

301

302 303

304

Figure 4 - Three TSN domains connected by Bridges

To support connectivity between multiple TSN domains (e.g. PLC L1 ↔ PLC M1) a method for reserving time-sensitive streams over multiple TSN domains needs to be specified, including:

- find the communication partner,
- identify the involved TSN domains,
- identify the involved management entities independent from the configuration model (centralized, hybrid, fully distributed),
- ensure the needed resources,
- parameterize the TSN domain connection points to allow stream forwarding if needed.

Use Cases For: IEEE P802.1DG Page 12 of 79

2.2.2.3 *Routers (Layer3)*

Together with routers, both intranet and internet are possible. In this sub-clause, however, only the intranet use case is addressed.

When a router is member of multiple TSN domains, one router interface/port must only be a member of a single TSN domain. Figure 5 provides an example of two routers, which are members of two TSN domains each. Router R1 provides ports and connectivity in TSN domain Production Cell 1 and in TSN domain Machine 1, Router R2 for Production Line 1 and Production Cell 1.

312


305

308

309

310

311



313314

315

316

317 318

319

320 321

322

Figure 5 - Three TSN domains connected by Routers

To support connectivity between multiple TSN domains (e.g. PLC L1 ↔ PLC M1) a method for reserving time-sensitive streams over multiple TSN domains needs to be specified, including:

- find the communication partner,
- identify the involved TSN domains,
- identify the involved management entities independent from the configuration model (centralized, hybrid, fully distributed).
- ensure the needed resources,
- parameterize the TSN domain connection points to allow stream forwarding if needed.

Use Cases For: IEEE P802.1DG Page 13 of 79

323 2.2.2.4 Application Gateways (Layer7)

327

328

329 330

334

335

336

337

338

339

340

341

342

- When an Application Gateway is member of multiple TSN domains, one gateway interface/port
- must only be a member of a single TSN domain.
- 326 Figure 6 provides an example of two application gateways:
 - Gateway CM1 is member in the TSN domains Production Cell 1 and Machine 1;
 - Gateway CF1 is member of the TSN domain Production Cell 1 and of Fieldbus 1.




Figure 6 – Gateways with two TSN domains and an attached Fieldbus

Application level gateways do not provide direct access between devices of different TSN domains.

Instead the application gateways act as end-stations for TSN domain egress and ingress
communication.

An application specific translation of control and data to access adjacent TSN domains may be implemented in the application level gateway to realize TSN domain interconnections. The translation may even involve buffering, collecting and re-arranging of data and control. Thereby application level gateways decouple TSN domains, so that the internal structure and configuration of adjacent TSN domains is not visible respectively.

Application level gateways are also used to connect non-Ethernet- or Ethernet-based fieldbuses to TSN domains (see Gateway CF1 in Figure 6 and see also Use case 11: Fieldbus gateway).

2.3 Synchronization

343 <<creator's note: What parts of this section from the Industrial Use Case document are applicable to 344 Automotive?>>

345 **2.3.1 General**

- Synchronization covering both universal time (wall clock) and working clock is needed for industrial automation systems.
- Redundancy for synchronization of universal time may be solved with "cold standby". Support of
- "Hot standby" for universal time synchronization is not current practice but may optionally be
- 350 supported depending on the application requirements.
- 351 Redundancy for working Clock synchronization can be solved with "cold standby" or "hot standby"
- depending on the application requirements. Support of "hot standby" for working clock
- 353 synchronization is current practice.

Use Cases For: IEEE P802.1DG Page 14 of 79

354 More details about redundancy switchover scenarios are provided in:

http://www.ieee802.org/1/files/public/docs2018/60802-Steindl-TimelinessUseCases-0718-v01.pdf.

2.3.2 Universal Time Synchronization

Universal time is used to plant wide align events and actions (e.g. for "sequence of events"). The assigned timescale is TAI, which can be converted into local date and time if necessary. Figure 7 shows the principle structure of time synchronization with the goal to establish a worldwide aligned timescale for time. Thus, often satellites are used as source of the time.




Figure 7 - plant wide time synchronization


Note: "Global Time" or "Wall Clock" are often used as synonym terms for "Universal Time".

2.3.3 Working Clock Synchronization

Working Clock is used to align actions line, cell or machine wide. The assigned timescale is arbitrary. Robots, motion control, numeric control and any kind of clocked / isochronous application rely on this timescale to make sure that actions are precisely interwoven as needed. Figure 8 shows the principle structure of Working Clock synchronization with the goal to establish a line / cell / machine wide aligned timescale. Thus, often PLCs, Motion Controller or Numeric Controller are used as Working Clock source.

If multiple PLCs, Motion Controller or Numeric Controller need to share one Working Clock timescale (e.g. for scheduled traffic), an all-time active station shall be used as Working Clock source, also known as Grandmaster.

Use Cases For: IEEE P802.1DG Page 15 of 79



375 376

377

378

379

380

Figure 8 - line/cell/machine wide working clock synchronization overlapping with a universal time domain

Working Clock domains may be doubled to support zero failover time for synchronization.

High precision working clock synchronization is a prerequisite for control loop implementations with low latency (see 3.1).

381 382

Requirements:

383 384

High precision working clock synchronization;

385

Maximum deviation to the grandmaster time in the range from 100 ns to 1 µs; Support of redundant sync masters and domains;

386

Zero failover time in case of redundant working clock domains:

387 388

Useful 802.1 mechanisms:

IEEE 802.1AS-Rev

389

390

391

2.3.4 Sequence of events 392

393

Sequence of events (SOE) is a mechanism to record timestamped events from all over a plant in a common database.

394 395 Application defined events are e.g. changes of digital input signal values. Additional data may be provided together with the events, e.g. universal time sync state and grandmaster, working clock domain and value ...

396 397

SOE enables root-cause analysis of disruptions after multiple events have occurred. Therefore SOE can be used as diagnostics mechanism to minimize plant downtime.

398

399 400

Plant-wide precisely synchronized time (see Figure 7) is a precondition for effective SOE application.

401

SOE support may even be legally demanded e.g. for power generation applications.

402

Requirements:

403 404 405

Plant wide high precision Universal Time synchronization;

Maximum deviation to the grandmaster time in the range from 1 us to 100 us: Optional support of redundant sync masters and domains;

Use Cases For: IEEE P802.1DG Page 16 of 79

406 Non-zero failover time in case of redundant universal time domains; 407 408 Useful 802.1 mechanisms: 409 IEEE 802.1AS-Rev 410 411 2.4 Redundancy 412 <<creator's note: Redundancy section was added.>> 413 2.5 Security 414 415 <<creator's note: Security section was added. What other sections are needed. As the Uses Cases are added to, this will become clearer.>> 416 417 418 2.6 Automotive traffic types 419 <<creator's note: I have moved the Use Cases section (data from presentations made at meetings/calls) 420 into a separate major heading section below. And I moved the Automotive Traffic Types here. The Traffic 421 Types is a very important topic that needs to be separated out. I see these use cases as the back-up 422 material that needs to be referenced by the summary/conclusions listed here & above.>> 423 **2.6.1 General** 424 <<creator's note: This section has not been updated. It is unchanged from the Industrial document. This 425 information has been left here so that readers can see the kinds of information we may need to document 426 and how the Use Cases drive decisions here (as show via references to the appropriate Use Cases).>> 427 428 Industrial automation applications concurrently make use of different traffic types for different functionalities, e.g. parameterization, control, alarming. The various traffic types have different 429 430 characteristics and thus impose different requirements on a TSN network. This applies for all use cases described in this document. 431

Use Cases For: IEEE P802.1DG Page 17 of 79

432

Table 1 - Industrial automation traffic types summary

Traffic type name	Periodic/ Sporadic	Guarantee	Data size	Redundancy	Details
isochronous cyclic real- time	Р	deadline/ bounded latency (e.g. 20%@1 Gbit/s / 50%@100 Mbit/s network cycle)/ bandwidth	bounded	up to seamless ¹⁾	see Table 4 and 3.1
cyclic real- time	Р	deadline/ bounded latency (e.g. n-times network cycle)/ bandwidth	bounded	up to seamless ¹⁾	see Table 8 and 3.3
network control	S	Priority	-	up to seamless ¹⁾ as required	see 2.2.2 and 3.7.1
audio/video	Р	bounded latency/ bandwidth	bounded	up to seamless ¹⁾ as required	-
brownfield	Р	bounded latency/ bandwidth	-	up to regular ²⁾	see 3.7.6
alarms/ events	S	bounded latency/ bandwidth	-	up to regular ²⁾	see 2.3.4
configuration/ diagnostics	S	Bandwidth	-	up to regular ²⁾	see 3.10.1
Internal / Pass-through	S	Bandwidth	-	up to regular ²⁾	see 3.8.2
best effort	S	-	-	up to regular ²⁾	-

¹⁾ almost zero failover time;

439 Isochronous:

433 434

435 436

437 438

440

441 442

443 444

445446

→ see section 2.3.3

In addition, if an isochronous application interface is needed: Machine vision application use cases for counting, sorting, quality control, video surveillance, augmented reality, motion guidance ...

Cyclic:

→ see Use case 03: Non-Isochronous Control Loops with bounded latency

Use Cases For: IEEE P802.1DG Page 18 of 79

²⁾ larger failover time because of network re-convergence

In addition, if a cyclic application interface is needed: Machine vision application use cases for counting, sorting, quality control, video surveillance, augmented reality, motion guidance ...

448 449 450

447

Network control:

→ see Use case 07: Redundant networks

451 452 453

Audio/video:

454

→ IEEE Std 802.1BA-2011 (AVB) may be supported in industrial automation as well

455 456

Brownfield:

457

→ see Use case 12: New machine with brownfield devices

458 459

Alarms/events:

460

→ see Sequence of events

461 462

Configuration/diagnostics:

463

→ see Use case 29: Network monitoring and diagnostics

464

Internal: 465

466

→ see Use case 18: Pass-through Traffic

467

Best effort:

468 469

→ see Use case 03: Non-Isochronous Control Loops with bounded latency.

470

Table 2 – isochronous cyclic real-time and cyclic real-time traffic type properties

Property	Description		
Data transmission scheme	Periodic (P) - e.g. every N μs, or Sporadic (S) - e.g. event-driven		
Data transmission constraints	Indicates the traffic pattern's data transmission constraints for proper operation. Four data transmission constraints are defined:		
	 deadline: transmitted data is guaranteed to be received at the destination(s) before a specific instant of time, 		
	 latency: transmitted data is guaranteed to be received at the destination(s) within a specific period of time after the data is transmitted by the sending application, 		
	 bandwidth: transmitted data is guaranteed to be received at the destination(s) if the bandwidth usage is within the resources reserved by the transmitting applications, 		
	 none: no special data transmission constraint is given. 		

Use Cases For: IEEE P802.1DG Page 19 of 79

Property	Description
Data period	For traffic types that transmit <i>periodic</i> data this property denotes according to the <i>data</i> transmission constraints:
	deadline: application data deadline period,
	latency, bandwidth or none: data transmission period.
	The period is given as a <i>range</i> of time values, e.g. 1μs 1ms.
	For the sporadic traffic types, this property does not apply.
Network access (data transmission) synchro-	Indicates whether the data transmission of sender stations is synchronized to the working clock (network cycle).
nized to working clock (network cycle)	Available property options are: yes, no or optional.
Application synchronized to	Indicates whether the applications, which make use of this traffic pattern, are synchronized to the network access.
network access	Available property options are: yes or no.
Acceptable jitter	Indicates for traffic types, which apply data transmission with <i>latency</i> constraints, the amount of jitter, which can occur and must be coped with by the receiving destination(s).
	For traffic types with <i>deadline, bandwidth</i> or <i>none</i> data transmission constraints this property is not applicable (<i>n.a.</i>).
Acceptable frame loss	Indicates the traffic pattern's tolerance to lost frames given e.g. as acceptable frame loss ratio range.
	The frame loss ratio value 0 indicates traffic types, where no single frame loss is acceptable.
Payload	Indicates the payload data type and size to be transmitted. Two payload types are defined:
	• fixed: the payload is always transmitted with exactly the same size
	 bounded: the payload is always transmitted with a size, which does not exceed a given maximum; the maximum may be the maximum Ethernet payload size (1500).

2.6.2 Bidirectional communication relations

471

472

473


474

475

476 477 The general behavior of field devices of process sensors and output signals is preconfigured and offers a set of services to a machine control unit. More complex field devices such as drives or machine parts have process data in both directions. If there are only outputs in a field device the stream back to the machine control is necessary for fast detection of problems in a field device. If there are only input process data the stream from the machine control to the field device is not necessary for normal operation.

The cell control communicates with the machine controls of the machines also in a bidirectional way.

Use Cases For: IEEE P802.1DG Page 20 of 79



481

483

484

486

487

488

489

490

491

492

495

496

499

500

501

502 503

480

Figure 9 - Bidirectional Communication

482 Requirements:

- Support of bidirectional streams;
- Sequence of actions how to establish such streams;

485 <u>Useful 802.1 mechanisms:</u>

IEEE 802.1Q (usage of streams)

2.6.3 Control Loop Basic Model

Control loops are fundamental building blocks of industrial automation systems. Control loops include: process sensors, a controller function, and output signals. Control loops may require guaranteed low latency or more relaxed bounded latency (see 3.3) network transfer quality.

To achieve the needed quality for Control loops the roundtrip delay (sometimes called makespan, too) of the exchanged data is essential.

493 494 ⁻

There are three levels of a control loop:

- Application within Talker/Listener,
- Network Access within Talker/Listener,
- Network Forwarding within Bridges.

498 Network Access is always synchronized to a common working clock or to a local timescale.

Application may or may not be synchronized to the synchronized Network Access depending on the application requirements. Applications which are synchronized to Network Access are called "isochronous applications". Applications which are not synchronized to Network Access are called "non-isochronous applications".

Network Forwarding may or may not be synchronized to a working clock depending on whether the Enhancements for Scheduled Traffic (IEEE Std 802.1Q-2018) are applied.

504 505

Use Cases For: IEEE P802.1DG Page 21 of 79




Figure 10 - Principle data flow of control loop

Transfer Times contain PHY and MAC delays. Both delays are asymmetric and vendor specific. Device vendors have to take into account these transfer times when their application cycle models are designed (see Figure 13).

Table 3 – Application types

Level	Isochronous Application		Non-i	sochronous Appli	cation
Application	Synchronized to network access Synchronized to local time			nescale	
Network access	Synchronized to working clock, Stream Class based scheduling, Preemption			Synchronized to local timescale, Stream Class based scheduling, Preemption	
	Synchronized to working clock	Free running	Synchronized to working clock	Free running	Free running
Network/Bridges	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Preemption	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Preemption	Strict Priority or other Shaper + Preemption

513514

506 507

508

509

510

511512

Use Cases For: IEEE P802.1DG Page 22 of 79

515 3 Automotive modes of operation – the Use Cases

Each use case below, starts with a link to its source material (if available). The words in each use case are the interpretations of the creator of this document. It is up to the author of the source material to make sure that this interpretation is correct. If so, it will be marked as 'Reviewed by original author'.

3.1 Use case 01: Example Automotive Networks

Source material: http://www.ieee802.org/1/files/public/docs2019/dg-zinner-automotive-architecture-evolution-0319-v02.pdf http://www.ieee802.org/1/files/public/docs2019/dg-zinner-automotive-architecture-evolution-0319-v02.pdf https://www.ieee802.org/1/files/public/docs2019/dg-zinner-automotive-architecture-evolution-0319-v02.pdf https://www.ieee802.org/1/files/public/docs2019/dg-zinner-automotive-architecture-evolution-0319-v02.pdf https://www.ieee802.org/1/files/public/docs2019/dg-zinner-automotive-architecture-evolution-0319-v02.pdf

3.1.1 Traditional Model

A traditional, or present day automotive network architecture for many can makers, is shown in Figure 11. These networks typically contain a Central Gateway ECU (top box in the figure) with point-to-point communion between all the application specific ECUs. Most ECU's are connected using non-Ethernet connections such as CAN, LIN, etc.

Ethernet links are limited to only those that require higher bandwidth (shown as the bold blue lines in the figure).




Figure 11 – Example of a Traditional or Central Gateway Automotive Network

3.1.2 Domain Model

An example of Domain automotive network architecture, is shown in Figure 12. Domain networks are the focus of many OEMs today. Ethernet is a clear enabler for these types of networks due to Ethernet's speeds and its support for the OSI Layer model.

Many OEMs want their ECU applications to communicate using IP so that the underlying physical connections are abstracted from the application. This allows a fully working ECU & application in one car model to be reused in another car model even if the underlying network is of a different speed and/or topology.

Domain networks can also work modularly. This allows a common architecture to work for full feature high-end cars, mid-range cars and low-end of a given model. For example, the ADAS ECU can be easily removed for those models that won't support autonomous driving. And/or the infotainment ECU can be scaled in quality/performance to meet the desired price point of the car.

Use Cases For: IEEE P802.1DG Page 23 of 79

Ethernet links can be used to connect the Domain Controllers (large top boxes in the figure) together (depending upon the link's needed bandwidth) where the figure shows possible redundancy support via the dotted line connection making a ring. Ethernet may be used more extensively below each Domain Controller as well (shown as the bold blue lines in the figure). Multiple connections to some ECU's are also shown. These connections could be for redundancy or one set of the connections could be from an ADAS ECU so that it can autonomously drive the car.




Figure 12 – Example of a Domain Automotive Network

<<creator's note: This Use Case summary is not completed yet!>>

3.1.3 Requirements from this use case (or Summary?)

<creator's note: It is the intention that the Requirements for each Use Case will be listed at the end of each Use Case. This way it acts as a summary. This approach may need to be adjusted as this document progresses.>>

<<creator's note: From here down, this section has not been updated. It is unchanged from the Industrial Use Case document. This information has been left here so that readers can see the kinds of information we may need in the form of Use Cases.>>

Use Cases For: IEEE P802.1DG Page 24 of 79

3.2 Use case 02: Isochronous Control Loops with guaranteed low latency

Control loops with guaranteed low latency implement an isochronous traffic pattern for isochronous applications, which are synchronized to the network access. It is based on application cycles, which consists of an IO data Transfer time and an Application time wherein the control loop function is executed. Figure 13 shows the principle how Network cycle, Transfer time and Application time interact in this use case.

Application cycle time and Network cycle time are identical in the example of Figure 13 (RR=1/see 3.4), whereas Figure 14 shows examples where the Application cycle time is longer than the Network cycle time (RR>1/see 3.4).

The control loop function starts for controllers and devices at a fixed reference point after the transfer time when all necessary buffers are available. A single execution of a control loop function ends before the next transfer time period starts. Thus, all frames shall be received by the addressed application within the transfer time. An optimized local transmit order at sender stations is required to achieve minimal transfer time periods.




Figure 13 – network cycle and isochronous application (Basic model)

Transfer Safety Margin is the maximum time, which is needed to transfer received data from the MDI reference plane (see Transfer Time (Receive)) to the application.

Application Safety Margin is the maximum time, which is needed to transfer the produced data from the application to the MDI reference plane (see Transfer Time (Transmit)).

Figure 14 shows how this principle is used for multiple concurrent applications with even extended computing time requirements longer than a single application time within the network cycle time. When reduction ratio >1 is applied (see 3.4), the control loop function can be expanded over multiple network cycles (Control loop 2 with reduction ratio 2 and Control loop 3 with reduction ratio 16 in Figure 14).

Maximum available computation time for a Control loop with reduction ratio X:

X * network cycle time – Transfer time – Application safety margin

Transfer of isochronous cyclic real-time, cyclic real-time and non-real-time data is processed in parallel to the various control loop functions - preserving the deadline requirement of the control loops.

A cyclic background task can additionally run, whenever spare Transfer or Application time is available.

Use Cases For: IEEE P802.1DG Page 25 of 79




Figure 14 - Multiple concurrent isochronous control loops (Extended model)

Network cycle: transfer time (including safety margin) and application time (including safety margin)

<u>Transfer time</u>: period of time, wherein all necessary frames are exchanged between stations (controller, devices); the minimum transfer time is determined by the e2e latencies of the necessary frames; the e2e latency depends on: PHY-, MAC-, cable-, bridge-delays and send ordering. The transfer time is a fraction of the network cycle time.

For a given target transfer time the number of possible bridges on the path is restricted due to PHY-, MAC-, cable- and bridge-delay contributions.

Figure 15 to Figure 20 show variations of the basic model of Figure 13:

In existing technologies some of the models are used in optimized ways to reduce the network cycle time and/or the IO-reaction time (sometimes also called 'makespan' or 'roundtrip delay time').




Figure 15 – Variation 1: two cycle timing model




Figure 16 - Variation 2: two cycle timing model - shifted by 180°

616617

618




Figure 17 - Variation 3: three cycle timing model

620

621

619




Figure 18 – Variation 4: one cycle timing model

623

624

622




Figure 19 - Variation 5: one cycle timing model - changed sequence

625626

627




Figure 20 - Variation 6: further optimizations

The extended model of Figure 14 may be applied to these variations as well.

629 630

631

632

628

3.2.1.1 Isochronous cyclic operation model

Figure 21 shows the isochronous cyclic operation model for guaranteed low latency.

Use Cases For: IEEE P802.1DG Page 27 of 79

633 634

Figure 21 – isochronous cyclic operation model

Device 22

Device 21

Device 20

Isochronous cyclic operation characteristics:

Device 12

Device 11

Device 10

Multiple applications (periodic tasks) with different application periods are supported. Applications are synchronized to working clock:

Devices: √Controller: √

Multiple application update times based on different reduction ratios are supported. Data transmission is synchronized to network cycle (WorkingClock):

Devices: √
Controller: √

The single steps of the isochronous cyclic operation model are:

Controller periodic tasks are synchronized to the working clock.

Example:

Periodic task 01 period (t1) == network cycle period (t2).

Periodic task_02 period (t1) == Network cycle period (t2).

Periodic task_02 period == 8 * network cycle period (t2).

Periodic task_03 period == 32 * network cycle period (t2).

Device data transmission is synchronized to network cycle (Working Clock).

Device input data shall reach controller within an application defined deadline. Controller application may check the timeliness (by means of additional data in the payload, e.g. LifeSign model).

Controller application operates on local process image data. Local process image decouples communication protocol from application.

Additional:

(3)

Device input data shall reach controller within a communication monitoring defined deadline (communication protocol). Communication disturbances are recognized and signaled asynchronously by communication protocol to application.

Use Cases For: IEEE P802.1DG Page 28 of 79

Controller output data transmission is synchronized to network cycle (Working Clock).



Controller output data shall reach device within an application defined deadline. Device application may check the timeliness (by means of additional data in the payload, e.g. PROFINET Isochronous Mode SignOfLife model – see [3]). Device application operates on local process image data. Local process image decouples communication protocol from application.

Additional:

Controller out data shall reach device within a communication monitoring defined deadline (communication protocol). Communication disturbances are recognized and signaled asynchronously by communication protocol to application.

High control loop quality is achieved by:

- Short network cycle times to minimize reaction time (dead time),
- equidistant network cycle times based on a synchronized working clock to ensure a defined reaction time,
- device signal processing and transfer coupled to synchronized working clock, and
- device and controller application (function) coupled to synchronized working clock.

<u>isochronous mode</u>: coupling of device and controller application (function) to the synchronized working clock

<u>isochronous cyclic real-time</u>: transfer time less than 20% (at link speeds > 100 Mbit/s) / 50% (at link speeds <= 100 Mbit/s) of network cycle and applications are coupled to the working clock.

Table 4 - isochronous traffic pattern properties

Characteristics **Notes** Data transmission scheme periodic deadline End-to-end one-way latency² less than 20% (link **Data transmission constraints** speeds > 100 Mbit/s) / 50% (link speeds <= 100 Mbit/s) of network cycle Data period 1μs .. 1ms 250μs ..4ms Network access (data Yes transmission) synchronized to working clock network cycle Application synchronized to Yes network access Acceptable jitter Deadline shall be kept n.a.

636 637

638

635

639 640 641

642

643 644 645

646647

Use Cases For: IEEE P802.1DG Page 29 of 79

² The end-to-end one-way latency is measured from the arrival of the last bit at the ingress edge port of the bridged

network to the transmission of the last bit by the egress edge port of the bridged network (see, e.g., Annex L.3 in IEEE Std 802.1Q-2018).

at link speed 1 Gbit/s (or higher)

To make short control loop times feasible PHY, MAC and bridge delays shall meet upper limits:

Figure 22 shows the definition of PHY delay, MAC delay and Bridge delay reference points.

MACTxDelay

Н

ı

M

xMII

MAC

Bridge delays shall be independent from the frame size and meet the upper limits of Table 7.

Internal Delay

BridgeDelay == bd

Figure 22 - delay measurement reference points

Strict numbers such as those proposed hereafter in Table 5, Table 6 and Table 7 are necessary to approach the problem of short control loop times. The numbers have to be agreed on in the profile.

Specifying these numbers, however, doesn't eliminate the need to publish exact values through

MACRxDelay

MAC

PHYRxDelay

Н

1

M

xMII

PHY

MDI

xMII

at link speed 100 Mbit/s

at link speed 10 Mbit/s

PHY delays shall meet the upper limits of Table 5.

MAC delays shall meet the upper limits of Table 6.

PHYTxDelay

PHY

Characteristics		Notes	
Acceptable frame loss	0n frames	Media redundancy requirements according to the required tolerance; e.g. seamless redundancy for value 0	
Payload	1 IEEE Std 802.3 maximum data payload size (i.e. 1500 bytes)	Data size negotiated during connection establishment	

648

649

Requirements on network cycle times:

1 µs to 1 ms

2 ms to 8 ms

250 µs to 4 ms

3.2.1.2 Delay requirements

650 651

652

653

654

655

657

656

658

660

659

662

6	6	3
6	6	4

661

Use Cases

802.1 standardized mechanisms as applicable.

MDI

For: IEEE P802.1DG

Page 30 of 79

665

Table 5 - Expected PHY delays

Device	RX delay ^C	TX delay ^C	Jitter
10 Mbit/s	<< 1 μs	<< 1 μs	< 4 ns
100 Mbit/s MII PHY	210 ns 90 ns (Max. 340 ns) ^a (Max. 140 ns) ^a		< 4 ns
100 Mbit/s RGMII PHY	210 ns ^b	90 ns ^b	< 4 ns
1 Gbit/s RGMII PHY	<< 500 ns ^b	<< 500 ns ^b	< 4 ns
2,5 Gbit/s RGMII PHY	<< 500 ns ^b	<< 500 ns ^b	< 4 ns
5 Gbit/s RGMII PHY	<< 500 ns ^b	<< 500 ns ^b	< 4 ns
10 Gbit/s	tdb tdb td		tdb
25 Gbit/s to 1 Tbit/s	tdb tdb tdb		tdb

^a According IEEE 802.3 for 100 Mbit/s full duplex with exposed MII.

666 667

Table 6 - Expected MAC delays

Link speed	Maximum RX delay	Maximum TX delay
10 Mbit/s	<< 1 µs	<< 1 µs
100 Mbit/s	<< 1 µs	<< 1 µs
1 Gbit/s	<< 1 μs	<< 1 μs
2,5 Gbit/s	<< 1 µs	<< 1 µs
5 Gbit/s	<< 1 µs	<< 1 µs
10 Gbit/s	<< 1 μs	<< 1 µs
25 Gbit/s - 1 Tbit/s	tdb	tdb

668 669

Table 7 - Expected Ethernet Bridge delays

Link speed	Value	Comment
10 Mbit/s	< 30 µs	No usage of bridging expected
100 Mbit/s	< 3 µs	Bridge delay measure from MII to MII ¹⁾
1 Gbit/s	< 1 µs	Bridge delay measure from RGMII to RGMII ¹⁾
2,5 Gbit/s	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
5 Gbit/s	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
10 Gbit/s	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
25 Gbit/s – 1 Tbit/s:	tdb	Bridge delay measure from XGMII to XGMII ¹⁾

670

Use Cases For: IEEE P802.1DG Page 31 of 79

^b Values from 100 Mbit/s PHYs (or better) are needed to allow substitution even for Gigabit or higher.

^C Lower values mean more performance for linear topology.

¹⁾ first bit in, first bit out

Useful 802.1 mechanisms:

• ..

Example:

A representative example of a "Control loop with guaranteed low latency" use case is given in clause 3.7.11.4 "Fast" process applications.

3.3 Use case 03: Non-Isochronous Control Loops with bounded latency

Control loops with bounded latency implement a cyclic traffic pattern for non-isochronous applications, which are not synchronized to the network access but are synchronized to a local timescale.

Figure 23 shows the principle how network cycle, transfer time and application time interact in this use case. The control loop function starts at an application defined time, which is not synchronized to the network access but to a local timescale. The network cycle, which describes the repetitive behavior of the network interface, may be synchronized to a common working clock or to a local timescale.





Figure 23 – network cycle and non-isochronous application (Basic model)

Extensions of this model analogous to Figure 14 (multiple applications with differing application lengths) are also possible.

Use Cases For: IEEE P802.1DG Page 32 of 79

3.3.1.1 Cyclic operation model



694 695 696

692

Figure 24 – cyclic operation model

Cyclic operation characteristics:

Multiple applications with different application periods are supported. Applications synchronized to a common working clock or a local timescale:

Devices: √
Controller: √

Multiple update times based on different reduction ratios are supported. Network access is synchronized to network cycle (WorkingClock):

Devices: √
Controller: √

The single steps of the cyclic operation model are:

1	Controller periodic tasks don't need to be synchronized to working clock, but may be synchronized.
	Periodic task period (t1) != network cycle period (t2).
2	Data transmission is synchronized to network cycle (Working Clock)
3	Device input data shall reach controller within a communication monitoring defined deadline (communication protocol).
	Controller application assumes a kept update interval but doesn't know whether it is kept or not.
	Communication disturbances are recognized and signaled asynchronously by communication protocol to application.
	Controller application operates on local process image data. Local process image decouples communication protocol from application.
4	Controller output data transmission is synchronized to network cycle (Working Clock).

Use Cases For: IEEE P802.1DG Page 33 of 79



Controller output data shall reach device within a communication monitoring defined deadline (communication protocol).

Device application assumes an kept update interval but doesn't know whether it is kept or not.

Communication disturbances are recognized and signaled asynchronously by communication protocol to application.

Device application operates on local process image data. Local process image decouples communication protocol from application.

698

700

701

702

703

704

705

706

707

708

699

3.3.1.2 Cyclic traffic pattern

L.3 in IEEE Std 802.1Q-2018).

Control loops with bounded latency implement a cyclic traffic pattern. More relaxed control reaction time requirements (e.g. 10 ms - 10 s) allow free running applications instead of isochronous applications. In consequence transfer time requirements are more relaxed as well. The transfer time may be longer than the network cycle in this use case.

For a given target transfer time the number of possible bridges on a communication path is restricted due to PHY-, MAC- and bridge-delay contributions, but can be much higher compared to Cyclic real-time: transfer time may be longer than network cycle and applications are decoupled from the working clock.

Table 8 - cyclic traffic pattern properties

Characteristics **Notes** Data transmission scheme periodic **Data transmission constraints** deadline End-to-end one-way latency³ less than X * network cycle (X | 1 .. n) Data period X * network cycle (X | 1 .. n) Network access (data Optional May be synchronized to local timescale instead transmission) synchronized to working clock (network cycle) Application synchronized to No synchronized to local timescale network access Acceptable jitter n.a. Deadline shall be kept Acceptable frame loss 0...n frames Media redundancy requirements according to the required tolerance; e.g. seamless redundancy for value 0 **Payload** 1 ... IEEE Std 802.3 maximum Data size negotiated during connection data payload size (i.e. 1500 establishment bytes)

Use Cases For: IEEE P802.1DG Page 34 of 79

709

³ The end-to-end one-way latency is measured from the arrival of the last bit at the ingress edge port of the bridged network to the transmission of the last bit by the egress edge port of the bridged network (see, e.g., Annex

710 Requirements:

3.4 Use case 04: Reduction ratio of network cycle

Application needs may limit the in principle flexible network cycle time to a defined granularity. E.g. in case of network cycle granularity 31,25 µs the possible network cycles are:

>= 1Gbit/s: 31,25 µs * 2ⁿ | n=0 .. 5 < 1Gbit/s: 31,25 µs * 2ⁿ | n=2 .. 7

Application cycle times are the result of the used network cycle times together with reduction ratios:

- 31,25 µs to 512 ms

<u>Reduction ratio</u>: The value of "reduction ratio" defines the number of network cycles between two consecutive transmits.

<u>Phase</u>: The value of "phase" in conjunction with "reduction ratio" defines the starting network cycle for the consecutive transmits.





Figure 25 - network cycle and application cycle

Use case 06: Drives without common application cycle but common network cycle is an example of multiple different application cycles, which are based on a common network cycle.

Figure 26 shows another example use case where all drives are connected in a line and every drive needs direct data exchange to the Controller and additionally to its direct neighbor. Some similar applications might even be more complex when the physical topology does not match the logical order of drives.

Use Cases For: IEEE P802.1DG Page 35 of 79



733734

739

740

Figure 26 - isochronous drive synchronization

735 Requirements:

736

737 Useful 802.1 mechanisms:

738 • ..

3.5 Use case 05: Drives without common application cycle

3.5.1.1 Background information


The cycle time requirements of different vendors may be based on their technology, which cannot be changed with reasonable effort. These requirements may be based on hardware dependencies, independent of the capabilities of the communication part of the device.

Figure 27 shows an example, where Vendor A needs to communicate with 31,25 µs between its devices (A1 with A2), and Vendor B needs to communicate with 50 µs (between B1 and B2).

The communication with the controller which has to coordinate both of them shall be a multiple of their local cycles. A1 needs to exchange data every 125µs with the Controller, B1 needs to exchange data every 200µs with the Controller.

Servo drives from different vendors (Vendor A and Vendor B) are working on the same network.
For specific reasons the vendors are limited in the choice of the period for their control loop.

Use Cases For: IEEE P802.1DG Page 36 of 79



751

Figure 27 – network with different application cycles

752 753

754

The following Communication Relations are expected to be possible:

755 Servodrive A1 ←→ Servodrive A2: 31,25 µs
 756 Servodrive B1 ←→ Servodrive B2: 50 µs
 757 Controller ←→ Servodrive A1: 125 µs
 758 Controller ←→ Servodrive B1: 200 µs

Servodrive A1 ←→Servodrive B1: 1 ms

760 761

762

763

764 765

759

Requirements:

Isochronous data exchange

 Different cycles for data exchange, which are not multiples of each other (cycles are not multiple of a common base, but fractions of a common base, here for instance 1 ms)

766 767

768

Useful 802.1Q mechanisms:

- Whatever helps
- ...

769 770

771


772

773

774

3.5.1.2 Controller communication

The Usecase concentrates on the communication between the devices A1 and B1, and the Controller as shown in Figure 28. Nevertheless the communication between A1/A2 and B1/B2 has to be solved as well.




775

Use Cases For: IEEE P802.1DG Page 37 of 79

778

Figure 28 - Multivendor Motion - Controller communication

3.5.1.3 Timing Requirements



779

Figure 29 - Multivendor Motion - Timing Requirements

780 781

782

783

The Controller runs 2 parallel programs in multitasking, one program with 125 µs cycle, and another with 200 µs cycle. Alternatively there might also be 2 independent controllers on the same network, one of vendor A and one of vendor B.

784 785 786

After every program execution, data needs to be exchanged between Controller and Servodrive. The time window for this exchange is application specific.

787 788 The actual data exchange on the wire can happen at any time in this window, the devices are not dependent on any exact transmission or reception timing, as long as the packet is in the scheduled window.

789 790

791

796

797

798

3.6 Use case 06: Drives without common application cycle but common network cycle

792 The concept of multiple different application cycles which are based on a common network cycle is 793

described in Use case 04: Reduction ratio of network cycle.

794 Examples with different application cycle times but common network cycle time 31,25 µs: 795

 $31,25 \mu s$ i.e. reduction ratio 1 for current control loop.

 $250 \mu s$, i.e. reduction ratio 8 for motor speed control loop,

1 ms. i.e. reduction ratio 32 for position control loop,

i.e. reduction ratio 512 for remote IO. 16 ms,

Use Cases For: IEEE P802.1DG Page 38 of 79




Figure 30 - different application cycles but common network cycle

799 800

801

802

Use Cases For: IEEE P802.1DG Page 39 of 79

3.7 Industrial automation networks

3.7.1 Use case 07: Redundant networks

803

804

805

806

807

808

813

814

816

817 818

821

822

823

Ring topologies are the basic industrial network architecture for switch-over or seamless redundancy.




Figure 31 - ring topology

When a production cell is also arranged in a ring topology the resulting architecture of cell with 809 810 attached machines is an interconnection of rings.

To even improve availability of the interconnection from the production cell into the machines this 811 link can be arranged redundantly as well (machine 1 in Figure 32): 812




Figure 32 - connection of rings

815 Requirement:

Support redundant topologies with rings.

Useful 802.1 mechanisms:

819 820

3.7.2 Use case 08: High Availability

High availability systems are composed of:

Redundant networks, and

Use Cases For: IEEE P802.1DG Page 40 of 79

- 824 Redundant stations.
- 825 E.g. tunnel control:

826 Tunnels need to be controlled by systems supporting high availability because airflow and fire 827 protection are crucial for the protection of people's lives. In this case PLC, remote IO and network 828

are installed to support availability in case of failure.




Figure 33 – example topology for tunnel control

831 Tunnel control may also include video surveillance as parallel application on the same network, 832 replacing dedicated analogue CCTV systems. This includes image processing applications like speed section control, detecting lost cargo or traffic in wrong direction with minimized detection 833 834 time.

835 Requirement:

829

830

837

838 839

840 841

842 843 844

846

847

848 849 850

836 Failure shall not create process disturbance – e.g. keep air flow active / fire control active.

The number of concurrent active failures without process disturbance depends on the application requirements and shall not be restricted by TSN profile definitions.

Parameter, program, topology changes need to be supported without disturbance.

Useful 802.1Q mechanisms:

- Redundancy for PLCs, Remote IOs and paths through the network

845 Further high availability control applications:

- Ship control
 - Power generation
- Power distribution

851 3.7.3 Use case 09: Wireless

- 852 HMI panels, remote IOs, wireless sensors or wireless bridges are often used in industrial
- 853 machines. Wireless connections may be based on IEEE 802.11 (Wi-Fi), IEEE 802.15.1 (Bluetooth),
- IEEE 802.15.4 or ITU/3GPP (5G). Even functional safety applications over wireless connections 854
- are supported (see Use case 25: Functional safety). 855

Use Cases For: IEEE P802.1DG Page 41 of 79




Figure 34 - HMI wireless connected using cyclic real-time




Figure 35 - Remote IO wireless connected using cyclic real-time




Figure 36 - Ring segment wireless connected for media redundancy

Requirement:

Support of wireless for

- cyclic real-time, and
- non-real-time communication

Useful 802.11 mechanisms:

- Synchronization support
- Extensions from .11ax
- ..

871 872

856

857

858

859

860

861

862 863

864

865

866

867 868

869 870

Use Cases For: IEEE P802.1DG Page 42 of 79

Weeful 802.15.1 mechanisms:

• .

874 875 876

Useful 802.1Q mechanisms:

• .

877 878

879

880

881

882 883

884

3.7.4 Use case 10: 10 Mbit/s end-stations (Ethernet sensors)

Simple and cheap sensor end-stations are directly attached via 10 Mbit/s links to the machine internal Ethernet and implement cyclic real-time communication with the PLC.

The support of additional physics like "IEEE 802.3cg APL support" is intended.




Figure 37 - Ethernet sensors

885 886

Requirement:

Support of 10 Mbit/s or higher link speed attached sensors (end-stations) together with POE and SPE (single pair Ethernet).

888 889 890

891

892

893

887

Useful 802.1Q mechanisms:

• ..

3.7.5 Use case 11: Fieldbus gateway

Gateways are used to integrate non-Ethernet and Ethernet-based fieldbusses into TSN domains.

Use Cases For: IEEE P802.1DG Page 43 of 79




Figure 38 - fieldbus gateways

Many systems have at least one merging unit (e.g gateway, multiplexer) between the sensors and actuators assigned to a single machine control. The clustering is typically done with some infrastructure elements (slices) that require a backplane communication. The fieldbus communication is in many cases the third level of communication. Thus, it is assumed that TSN is not the first communication network between the sensors/actuators and a machine control unit. This means that TSN should be capable to adapt an existing communication infrastructure regardless of the size of those networks. The networks behind a gateway have their own timing constraints. A machine level network may take into account that the lower level networks e.g. behind a gateway have their own local timing. The timing of a TSN network has impact to subordinated structures. An optimal timing requires taking into account the gateway behavior for the TSN configuration (see Figure 39).




Figure 39 - Embedded non TSN communication

Requirement:

 Support of non-Ethernet and Ethernet-based fieldbus devices via gateways either transparent or hidden;

Use Cases For: IEEE P802.1DG Page 44 of 79

TSN scheduling may need configuration to meet the requirements of subordinate systems;

3.7.6 Use case 12: New machine with brownfield devices

Brownfield devices with real-time communication are attached to a PLC, which supports both brownfield and greenfield, within a machine. This allows faster deployment of devices supporting the TSN-IA profile into the field. Figure 40 gives an example of a machine with brownfield devices.




Figure 40 - New machine with brownfield devices

Requirement:

All machine internal stream traffic communication (stream traffic <u>and</u> non-stream traffic) is decoupled from and protected against the brownfield cyclic real-time traffic. Brownfield cyclic real-time traffic QoS is preserved within the TSN domain.

Useful 802.1Q mechanisms:

- · Priority Regeneration,
- separate "brownfield traffic queue".
- Queue-based resource allocation.

Figure 41 shows a different use case where a TSN machine is attached to an existing brownfield machine. In this case only non-TSN traffic is possible between the two machines.




Figure 41 - Add TSN machine to brownfield machine

Use Cases For: IEEE P802.1DG Page 45 of 79

3.7.7 Use case 13: Mixed link speeds

Industrial use cases refer to link speeds, as shown in Table 9, in the range from 10 Mbit/s to 10 GBit/s for Ethernet and additional Wi-Fi, Bluetooth and 5G. Thus, the TSN domains need to handle areas with different link speeds.


938 Table 9 – Link speeds

Link speed	Media	Comments
100 kbit/s - 3 Mbit/s	Radio Bluetooth	These devices are connected thru a Bluetooth access point. They may be battery powered.
1 Mbit/s – 1 Gbit/s	Radio Wi-Fi	These devices are connected thru a Wi-Fi access point. They may be battery powered.
1 Mbit/s - 10 Gbit/s (theoretical/expected)	Radio 5G	These devices are connected thru a 5G access point. They may be battery powered.
10 Mbit/s	Copper or fiber	May be used for end station "only" devices connected as leafs to the domain. Dedicated to low performance and lowest energy devices for e.g. process automation. These devices may use PoE as power supply.
100 MBit/s	Copper or fiber	Historical mainly used for Remote IO and PLCs. Expected to be replaced by 1 GBit/s as common link speed.
1 GBit/s	Copper or fiber	Main used link speed for all kind of devices
2,5 GBit/s	Copper or fiber	High performance devices or backbone usage
5 GBit/s	Copper or fiber	Backbone usage, mainly for network components
10 GBit/s	Fiber	Backbone usage, mainly for network components
25 GBit/s - 1 Tbit/s	tbd	Backbone usage, mainly for network components

Mixing devices with different link speeds is a non-trivial task. Figure 42 and Figure 43 show the calculation model for the communication between an IOC and an IOD connected with different link speeds.

The available bandwidth on a communication path is determined by the path segment with the minimum link speed.

The weakest link of the path defines the usable bandwidth. If a topology guideline ensures that the connection to the end-station always is the weakest link, only these links need to be checked for the usable bandwidth.



Use Cases For: IEEE P802.1DG Page 46 of 79

949

950

952

953

954

955

959 960

961

962

963

964

Figure 42 - mixed link speeds

Available bandwidth = minimum linkspeed (path) = 100 Mbit/s

2,5 Gbit/s

Machine

951

Figure 43 – mixed link speeds without topology guideline

Requirement:

Links with different link speeds as shown in Figure 42 share the same TSN-IA profile based communication system at the same time.

Links with different link speeds without topology guideline (Figure 43) may be supported.

956 957

Useful 802.1 mechanisms:

958 • .

3.7.8 Use case 14: Multiple isochronous domains

Figure 44 shows a machine which needs due to timing constraints (network cycle time together with required topology) two or more separated isochronous real-time domains but shares a common cyclic real-time domain.

Both isochronous domains may have their own Working Clock and network cycle. The PLCs need to share remote IOs using cyclic real-time traffic.




Figure 44 - multiple isochronous domains

Some kind of coupling (e.g. shared synchronization) between the isochronous domains / Working Clocks may be used (see Figure 45).

All isochronous domains may have different network cycle times, but the cyclic real-time data exchange shall still be possible for PLCs from both isochronous domains.

Use Cases For: IEEE P802.1DG Page 47 of 79

965

966

967

968

969

970




Figure 45 - multiple isochronous domains - coupled

Requirements:

Isochronous real-time domains may run independently, loosely coupled (start of network cycle is synchronized) or tightly coupled (shared working clock). They shall be able to share a cyclic real-time domain.

Useful 802.1 mechanisms:

- separate "isochronous" and "cyclic" traffic queues,
- · Queue-based resource allocation in all bridges,
- ...

3.7.9 Use case 15: Auto domain protection

Machines are built in a way that not always all devices are really attached either due to different machine models/variants or repair. In this use case a TSN domain shall not expand automatically when e.g. two machines get connected via an unplanned and unintended link.




Figure 46 - Auto domain protection

Use Cases For: IEEE P802.1DG Page 48 of 79

996 3.7.10 Use case 16: Vast number of connected stations 997 Some industrial applications need a massive amount of connected stations like 998 - Postal, Parcel and Airport Logistics 1000 1001 Examples for "Airport Logistics": • Incheon International Airport, South Korea 1003 • Guangzhou Baiyun International Airport, China 1004 • London Heathrow Airport, United Kingdom 1005 • Dubai International Airport, UAE 1006 • 1007 1008 Dubai International Airport, UAE 1009 Technical Data: • 100 km conveyor length 1011 • 222 check-in counters 1012 • car park check-in facilities 1013 • Max. tray speed: 7.5 m/s 1014 • 49 make-up carousels 1015 • 14 baggage claim carousels 1016 • 24 transfer laterals 1017 • Storage for 9,800 Early Bags 1018 • Employing 48 inline screening 1019 • Max. 8-stories rack system 1020 • 10,500 ton steel 1021 • 234 PLC's 1022 • 16,500 geared drives 1023 • [xxxx digital lOs] Further representative examples of required quantities are provided in 3.7.11.1 and 3.7.11.2.	990 991 992 993 994 995	Requirement: Support of auto TSN domain protection to prevent unintended use of traffic classes Useful 802.1Q mechanisms: Priority regeneration
 Incheon International Airport, South Korea Guangzhou Baiyun International Airport, China London Heathrow Airport, United Kingdom Dubai International Airport, UAE United Margort Dubai International Airport, UAE Technical Data: 100 km conveyor length 222 check-in counters car park check-in facilities Max. tray speed: 7.5 m/s 49 make-up carousels 14 baggage claim carousels 24 transfer laterals Storage for 9,800 Early Bags Employing 48 inline screening Max. 8-stories rack system 10,500 ton steel 234 PLC's 16,500 geared drives [xxxx digital IOs] Further representative examples of required quantities are provided in 3.7.11.1 and 3.7.11.2. 	997 998 999	Some industrial applications need a massive amount of connected stations like - Car production sites - Postal, Parcel and Airport Logistics
Dubai International Airport, UAE Technical Data: 1010	1002 1003 1004 1005 1006	 Incheon International Airport, South Korea Guangzhou Baiyun International Airport, China London Heathrow Airport, United Kingdom Dubai International Airport, UAE
 1015 14 baggage claim carousels 24 transfer laterals 1017 Storage for 9,800 Early Bags Employing 48 inline screening 1019 Max. 8-stories rack system 1020 10,500 ton steel 234 PLC's 1022 16,500 geared drives [xxxx digital IOs] Further representative examples of required quantities are provided in 3.7.11.1 and 3.7.11.2. 	1009 1010 1011 1012 1013	Technical Data: • 100 km conveyor length • 222 check-in counters • car park check-in facilities • Max. tray speed: 7.5 m/s
 1022 16,500 geared drives [xxxx digital IOs] [uther representative examples of required quantities are provided in 3.7.11.1 and 3.7.11.2. 	1016 1017 1018 1019 1020	 24 transfer laterals Storage for 9,800 Early Bags Employing 48 inline screening Max. 8-stories rack system 10,500 ton steel
4007	1022 1023 1024 1025 1026	 16,500 geared drives [xxxx digital IOs] Further representative examples of required quantities are provided in 3.7.11.1 and 3.7.11.2.
requirement.	1028 1029 1030 1031	Make sure that even this massive amount of stations works together with the TSN-IA profile. This kind of applications may or may not require wireless support, too. <u>Useful 802.1 mechanisms:</u>

Use Cases For: IEEE P802.1DG Page 49 of 79

1033 3.7.11 Minimum required quantities


1034 3.7.11.1 A representative example for VLAN requirements

- Figure 47 shows the IEEE 802.1Q based stacked physical, logical and active topology model. This principle is used to build TSN domains.
- 1037 It shows the different active topologies driven by either VID (identified by VLAN) or protocol 1038 (identified by DA-MAC and/or protocol type).
- Additionally the number of to be supported VIDs per bridge is shown. The number of protocol agent defined active topologies is just an example because e.g. LLDP, RSTP or MST is missing.
- The following topologies, trees and VLANs are shown in Figure 47.

0	Physical network topology	all existing devices and links
0	Logical network topology	TSN domain : administrative selection of elements from the physical topology
2	Active default topology	Default VLAN: result of a spanning tree algorithm (e.g. RSTP)
8	Cyclic RT	VLAN for cyclic real-time streams
4	Cyclic RT "R"	VLAN for redundant cyclic real-time streams
6	Isochronous cyclic RT 1	VLAN for isochronous cyclic real-time streams
6	Isochronous cyclic RT 1 "R"	VLAN for redundant isochronous cyclic real-time streams
0	Isochronous cyclic RT 24	VLAN for isochronous cyclic real-time streams
8	Working clock	gPTP sync tree used for the synchronization of a working clock
0	Working clock "R"	Hot standby gPTP sync tree used for the synchronization of a working clock
00	Universal time	gPTP sync tree used for the synchronization of universal time

Use Cases For: IEEE P802.1DG Page 50 of 79

⁴ The isochronous cyclic RT 2 "R" is not applied in this example but can be made available additionally



1042

Use Cases For: IEEE P802.1DG Page 51 of 79

Figure 47 – Topologies, trees and VLANs

1043

Use Cases For: IEEE P802.1DG Page 52 of 79

1044 1045

1046

1050

Expected numbers of DA-MAC address entries used together with five VLANs (Default, High, High Redundant, Low and Low Redundant) are shown in Table 10 and Table 11.

Table 10 may be implemented as FDB table with a portion of DA-MAC address (e.g. 12 bits of Identifier and TSN-IA profile OUI) as row and the VLANs as column to ensure availability of a dedicated entry.

Table 10 - Expected number of stream FDB entries

# of VLANs	# of DA-MACs	Usage
4		Numbers of DA-MAC address entries used together with four VLANs (High, High Red, Low and Low Red)

1051 1052

1053

1054

Expected number of entries is given by the maximum device count of 1024 together with the 50% saturation due to hash usage rule. Table 11 shows the expected number of possible FDB entries.

Table 11 - Expected number of non-stream FDB entries

# of VLANs	# of entries	Usage
1	2 048	Learned and static entries for both, Unicast and Multicast

1055 1056

1057

The hash based FDBs shall support a neighborhood for entries according to Table 12.

Table 12 – Neighborhood for hashed entries

Neighborhood	Usage
	Default
8	A neighborhood of eight entries is used to store a learned entry if the hashed entry is already used.
	A neighborhood of eight entries for the hashed index is check to find or update an already learned forwarding rule.

1058

1059 1060

1061

10621063

1064

1065

1066

1067

1068 1069

1070

1071

3.7.11.2 A representative example for data flow requirements

TSN domains in an industrial automation network for cyclic real-time traffic can span multiple Cyber-physical systems, which are connected by bridges. The following maximum quantities apply:

- Stations: 1024
 - Network diameter: 64
 - per PLC for Controller-to-Device (C2D) one to one or one to many communication:
 - 512 producer and 512 consumer data flows; 1024 producer and 1024 consumer data flows in case of seamless redundancy.
 - 64 kByte Output und 64 kByte Input data
 - per Device for Device-to-Device (D2D) one to one or one to many communication:
 - 2 producer and 2 consumer data flows; 4 producer and 4 consumer data flows in case of seamless redundancy.
 - o 1400 Byte per data flow

Use Cases For: IEEE P802.1DG Page 53 of 79

1072 per PLC for Controller-to-Controller (C2C) – one to one or one to many – communication: 1073 o 64 producer and 64 consumer data flows; 128 producer and 128 consumer data flows in 1074 case of seamless redundancy. 1400 Byte per data flow 1075 1076 Example calculation for eight PLCs 1077 \rightarrow 8 x 512 x 2 = 8192 data flows for C2D communication = 1024 data flows for C2C communication 1078 \rightarrow 8 x 64 x 2 1079 → 8 x 64 kByte x 2 = 1024 kByte data for C2D communication 1080 \rightarrow 8 x 64 x 1400 Byte x 2 = 1400 kByte data for C2C communication 1081 All above shown data flows may optionally be redundant for seamless switchover due to the 1082 need for High Availability. 1083 Application cycle times for the 512 producer and 512 consumer data flows differ and follow the application process requirements. 1084 1085 E.g. 125 us for those used for control loops and 500 us to 512 ms for other application processes. 1086 All may be used concurrently and may have frames sizes between 1 and 1440 bytes. 1087 3.7.11.3 A representative example of communication use cases 1088 IO Station – Controller (input direction) Up to 2000 published + subscribed signals (typically 100 – 500) 1089 1090 Scan interval time: 0,5 .. 100ms (typical 10ms) Controller – Controller (inter-application) 1091 1092 Up to 1000 published + subscribed signals (typically 100 – 250) 1093 Application task interval time: 10..1000ms (typical 100ms) 1094 - Resulting Scan interval time: 5 ... 500 ms 1095 Closing the loop within/across the controller 1096 Up to 2000 published + subscribed signals (typically 100 – 500) Application task interval time: 1..1000ms (typical 100ms) 1097 0,5 ... 500 ms 1098 - Resulting Scan interval time when spreading over controllers:

1099 Controller – IO Station (output direction)

- Up to 2000 published + subscribed signals (typically 100 500)
- 1101 Application task interval time: 10..1000ms (typical 100ms
- 1102 Resulting Scan interval time: 5 ... 500 ms

1103


1100

1104 3.7.11.4 "Fast" process applications

The structure shown in **Error! Reference source not found.** applies. Figure 48 provides a logic

1106 station view.

Use Cases For: IEEE P802.1DG Page 54 of 79



1107 1108

1110

1111

1112 1113

1114

Figure 48 - Logical communication concept for fast process applications

1109 Specifics:


- Limited number of nodes communicating with one Controller (e.g. Turbine Control)
- Up to a dozen Nodes of which typically one is a controller
- Data subscriptions (horizontal):
 - 270 bytes published + subscribed per IO-station
 - Scan Interval time 0,5 to 2 ms
 - Physical Topology: Redundant (as path and as device)

1115 1116

1117

3.7.11.5 Server consolidation

The structure shown in Error! Reference source not found. applies. Figure 49 provides a logic 1118 1119 station view.



1120

Figure 49 - Server consolidated logical connectivity

1121 1122

Data access to Operations Functionalities consolidated through Servers

- 1123 1124
- Up to 100 Nodes in total
- 1125
- Out which are up to 25 Servers

1126

Use Cases For: IEEE P802.1DG Page 55 of 79


- 1127 Data subscriptions (vertical):
- 1128 Each station connected to at least 1 Server
- 1129 max. 20000 subscribed items per Controller/IO-station
- 1130 1s update rate
- 1131 50% analog items -> 30% change every sec

1132

- 1133 Different physical topologies
- 1134 Rings, stars, redundancy

1135

- **1136 3.7.11.6 Direct client access**
- 1137 The structure shown in **Error! Reference source not found.** applies. Figure 50 provides a logic station view.



11391140

Figure 50 - Clients logical connectivity view

- 1141 Data access to Operations Functionalities directly by Clients
- 1142 Max 20 direct access clients

1143

- 1144 Data subscriptions (vertical):
- 1145 Up to 3000 subscribed items per client
- 1146 1s update rate
- 1147 Worst case 60000 items/second per controller in classical Client/Server setup
- 1148 50% analog items -> 30% change every sec

1149

- 1150 Different physical topologies
- 1151 Rings, stars, redundancy

1152

Use Cases For: IEEE P802.1DG Page 56 of 79

1153 3.7.11.7 Field devices

The structure shown in **Error! Reference source not found.** applies. Figure 51 provides a logic station view.




Figure 51 - Field devices with 10Mbit/s

1158 1159

1156 1157

1154

1155

Field Networks integrated with converged network

1160 - Up to 50 devices per field segment

- Scan interval 50ms ... 1s, typical 250ms
- Mix of different device types from different vendors
- Many changes during runtime

1163 1164

1167

1168

1169

1170

11611162

1165 3.7.12 Bridge Resources

The bridge shall provide and organize its resources in a way to ensure robustness for the traffic defined in this document as shown in Formula [1].

The queuing of frames needs resources to store them at the destination port. These resources may be organized either bridge globally, port globally or queue locally.

The chosen resource organization model influences the needed amount of frame resources.

1171 1172

For bridge memory calculation Formula [1] applies.

 $MinimumFrameMemory = (NumberOfPorts - 1) \times MaxPortBlockingTime \times Linkspeed$ (1)

Where

MinimumFrameMemory is minimum amount of frame buffer needed to avoid frame loss from non stream traffic due to streams blocking egress ports.

NumberOfPorts is number of ports of the bridge without the management port.

MaxPortBlockingTime is intended maximum blocking time of ports due to streams per millisecond.

Use Cases For: IEEE P802.1DG Page 57 of 79

Linkspeed

is intended link speed of the ports.

1173 1174 1175

1176

1177

1178

1179

Formula [1] assumes that all ports use the same link speed and a bridge global frame resource management. Table 13, Table 14, Table 15, and Table 16 shows the resulting values for different link speeds and fully utilized links.

The traffic from the management port to the network needs a fair share of the bridge resources to ensure the required injection performance into the network. This memory (use for the real-time frames) is not covered by this calculation.

1180

Table 13 - MinimumFrameMemory for 100 Mbit/s (50%@1 ms)

# of ports	MinimumFrameMemory [KBytes]	Comment
1	0	The memory at the management port is not covered by Formula [1]
2	6,25	All frames received during the 50%@1 ms := 500 µs at one port needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
3	12,5	All frames received during the 50%@1 ms := 500 µs at two ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
4	18,75	All frames received during the 50%@1 ms := 500 µs at three ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
other	tbd	tbd

1181 1182

Table 14 - MinimumFrameMemory for 1 Gbit/s (20%@1 ms)

# of ports	MinimumFrameMemory [KBytes]	Comment
1	0	The memory at the management port is not covered by Formula [1]
2	25	All frames received during the 20%@1 ms := 200 µs at one port needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
3	50	All frames received during the 20%@1 ms := 200 µs at two ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
4	75	All frames received during the 20%@1 ms := 200 µs at three ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
other	tbd	tbd

11831184

Table 15 - MinimumFrameMemory for 2,5 Gbit/s (10%@1 ms)

# of ports	MinimumFrameMemory [KBytes]	Comment
1	0	The memory at the management port is not covered by Formula [1]
2	31,25	All frames received during the 10%@1 ms := 100 µs at one port needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.

Use Cases For: IEEE P802.1DG Page 58 of 79

# of ports	MinimumFrameMemory [KBytes]	Comment
3	62,5	All frames received during the 10%@1 ms := 100 µs at two ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
4	93,75	All frames received during the 10%@1 ms := 100 µs at three ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
other	tbd	tbd

11851186

Table 16 - MinimumFrameMemory for 10 Gbit/s (5%@1 ms)

# of ports	MinimumFrameMemory [KBytes]	Comment
1	0	The memory at the management port is not covered by Formula [1]
2	62,5	All frames received during the $5\%@1$ ms := $50 \mu s$ at one port needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
3	125	All frames received during the 5%@1 ms := 50 µs at two ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
4	187,5	All frames received during the 5%@1 ms := 50 µs at three ports needed to be forwarded to the other port are stored during the allocation of this port due to stream transmission.
other	tbd	tbd

1187 1188

1189

1190

1191

1192

1193

1194

1195

1196

A per port frame resource management leads to the same values, but reduces the flexibility to use free frame resources for other ports.

A per queue per port frame resource management would increase (multiplied by the number of to be covered queues) the needed amount of frame resources dramatically almost without any benefit.

Example "per port frame resource management":

100 Mbit/s, 2 Ports, and 6 queues

Needed memory := 6,25 KOctets * 6 := 37,5 KOctets.

No one is able to define which queue is needed during the "stream port blocking" period.

1197 1198 1199

1200

Bridged End-Stations need to ensure that their local injected traffic does not overload its local bridge resources. Local network access shall conform to the TSN-IA profile defined model with management defined limits and cycle times (see e.g. row Data period in Table 4).

Use Cases For: IEEE P802.1DG Page 59 of 79

3.8 Industrial automation machines, production cells, production lines

3.8.1 Use case 17: Machine to Machine/Controller to Controller (M2M/C2C) Communication

Preconfigured machines with their own TSN domains, which include tested and approved internal communication, communicate with other preconfigured machines with their own TSN domains, with a supervisory PLC of the production cell (with its own TSN domain) or line (with its own TSN domain) or with an Operations Control HMI (with its own TSN domain).




Figure 52 - M2M/C2C between TSN domains

Figure 52 shows that multiple logical overlapping TSN Domains arise, when controllers use a single interface for the M2M communication with controllers of the cell, line, plant or other machines. Decoupling of the machine internal TSN Domain can be accomplished by applying a separate controller interface for M2M communication.

- Machine 1: the controller link to its connected cell bridge B1 is concurrently member of the TSN Domains of Machine 1, Production Cell 1, Production Line and Plant.
- Machine 2: the controller link to its connected cell bridge B2 is concurrently member of the TSN Domains of Machine 2, Production Cell 1 and Plant.
- Machine 3: the controller is directly attached to the PLC of Production Cell 2 and is therefore member of the TSN Domain of Production Cell 2. The machine internal TSN Domain is decoupled from M2M traffic by a separate interface.
- Machine 4: the controller link to its connected cell bridge B3 is concurrently member of the TSN Domains of Production Cell 2 and Plant. The machine internal TSN Domain is decoupled from M2M traffic by a separate interface.

Examples:

Use Cases For: IEEE P802.1DG Page 60 of 79

1225




Figure 53 gives an example of M2M communication to a supervisory PLC.

Figure 54 shows an example of M2M communication relations between four machines.

PLCs with one single interface lead to overlapping communication paths of M2M and machine internal traffic. In this case two TSN domains (Machine / Production cell) need to share resources due to two logical overlapping TSN domains.

Figure 53 - M2M with supervisory PLC

There are quite a few constraints related to the machine internal networks. Each machine may run a different schedule and even the intervals may be different. It may be very complex or even impossible to find an optimal communication schedule down from the sensors and actuators to the cell control. The requirements for cascaded control loops require faster intervals for the lower control loops. The multiple machine intervals embedded in one cell interval can be mapped onto a sequence of intervals. Each step in the exchange of data between machine and cell control unit can be mapped into machine intervals:

- outbound cell communication,
- transfer outbound within machine network,
- transfer inbound within machine network.
- inbound cell communication.

Additionally Figure 55 shows an example where M2M communication is used to connect a PC for diagnostics/monitoring.




Figure 54 - M2M with four machines

Use Cases For: IEEE P802.1DG Page 61 of 79




Figure 55 - M2M with diagnostics/monitoring PC

- Figure 55 shows a M2M diagnostics related use case: communication is cyclic and shall happen
- within short application cycle times. An example of this use case is the verification of proper
- behavior of a follower drive, in a master-follower application. Today, the use case is covered by
- 1229 connecting a common PC to an interface of the follower drive. The various TSN mechanisms may
- now make it possible to connect such a PC network interface card anywhere in the system network
- and still gather the same diagnostics with the same guarantees, as the current direct connection.
- 1232 The required guarantees are:
- 1233 Each 4 ms a frame shall be sent from a follower drive and have its delivery guaranteed to the
- network interface of the PC used to perform the diagnostics. Of course, local PC-level processing
- of such frames has to be implemented such that the diagnostic application gets the required quality
- 1236 of service.
- From the communication point of view the two types of machine interface shown in Figure 54 are
- identical. The PLC represents the machine interface and uses either a dedicated (machine 1 and 4)
- or a shared interface (machine 2 and 3) for communication with other machines and/or a
- supervisor PLC.
- The communication relations between machines may or may not include or make use of a
- supervisory PLC.

1243 Requirement:

1244

1245

1246

1247

1248

1249 1250

1251

1252

1255

- All machine internal communication (stream traffic and non-stream traffic) is decoupled from and protected against the additional M2M traffic and vice versa.
- 1:1 and 1:many communication relations shall be possible.
- Scheduling in a way that interleaved operation with machine intervals is possible.

Useful 802 mechanisms:

- IEEE Std 802.1Q-2018, Fixed priority, IEEE Std 802.3br
- Priority Regeneration,
- Queue-based resource allocation,
- VLANs to separate TSN domains.

3.8.2 Use case 18: Pass-through Traffic

Machines are supplied by machine builders to production cell/line builders in tested and approved quality. At specific boundary ports standard devices (e.g. barcode reader) can be attached to the

Use Cases For: IEEE P802.1DG Page 62 of 79

1256 1257

1258

1259

machines. The machines support transport of non-stream traffic through the tested/approved machine ("pass-through traffic") without influencing the operational behavior of the machine, e.g. connection of a printer or barcode reader. Figure 56, Figure 57 and Figure 58 give some examples of pass-through traffic installations in industrial automation.




Figure 56 - pass-through one machine




Figure 57 – pass-through one machine and production cell




Figure 58 - pass-through two machines




Figure 59 - machine with diagnostics / monitoring PC

1260 Requirement:

1263

1261 <u>All</u> machine internal communication (stream traffic <u>and</u> non-stream traffic) is decoupled from and protected against the additional "pass-through" traffic.

"Pass-through" traffic is treated as separate traffic pattern.

Use Cases For: IEEE P802.1DG Page 63 of 79

1264 1265

1266

1267

1268

Useful 802.1Q mechanisms:

- Priority Regeneration,
- separate "pass-through traffic queue",
- · Queue-based resource allocation in all bridges,
- Ingress rate limiting.

1269 1270

1271 1272

1273

1274

1275

1276


3.8.3 Use case 19: Modular machine assembly


In this use case machines are variable assemblies of multiple different modules. Effective assembly of a machine is executed in the plant dependent on the current stage of production, e.g. bread-machine with the modules: base module, 'Kaisersemmel' module, 'Rosensemmel' module, sesame caster, poppy-seed caster, baking oven OR advertisement feeder for newspapars.

Figure 60 may have relaxed latency requirements, but the machine in Figure 61 needs to work with very high speed and thus has very demanding latency requirements.

12771278

1279





12801281

Figure 60 - modular bread-machine

Use Cases For: IEEE P802.1DG Page 64 of 79




Figure 61 – modular advertisement feeder

Requirement:

Modules can be assembled to a working machine variably on-site (either in run, stop or power down mode) as necessary (several times throughout a day). The machine produces the selected variety of a product. Communication relying on TSN features is established automatically after the modules are plugged without management/ configuration interaction.

3.8.4 Use case 20: Tool changer

Tools (e.g. different robot arms) are in power off mode. During production a robot changes its arms for different production steps.

They get mechanically connected to a robot arm and then powered on. The time till operate influences the efficiency of the robot and thus the production capacity of the plant. Robots may share a common tool pool. Thus the "tools" are connected to different robots during different production steps.




Figure 62 - tool changer

Use Cases For: IEEE P802.1DG Page 65 of 79

1299 1300

Requirement:

1301 1302

Added portion of the network needs to be up and running (power on to operate) in less than 500ms.

1303

Extending and removing portions of the network (up to 16 devices) in operation

1304 1305

by one connection point (one robot using a tool)

o by multiple connection points (multiple robots using a tool)

1306 1307

Useful 802.1Q mechanisms:

- 1308 1309
- preconfigured streams


1310

1311 3.8.5 Use case 21: Dynamic plugging and unplugging of machines (subnets)

1312 1313

- E.g. multiple AGVs (automatic guided vehicles) access various docking stations to get access to the supervisory PLC. Thus, an AGV is temporary not available. An AGV may act as CPS or as a
- bunch of devices. 1314

1315



1316

Figure 63 - AGV plug and unplug

1317 1318

Requirement:

1319 1320

The traffic relying on TSN features from/to AGVs is established/removed automatically after plug/unplug events.

- Different AGVs may demand different traffic layouts. 1321
- 1322 The time till operate influences the efficiency of the plant.

1323 Thousands of AGS may be used concurrently, but only a defined amount of AGVs is connected at 1324 a given time.

1325 1326

1327

1328

Useful 802.1Q mechanisms:

- preconfigured streams
- 1329

1330 1331

> **Use Cases** For: IEEE P802.1DG Page 66 of 79

1332 3.8.6 Use case 22: Energy Saving

Complete or partial plant components are switched off and on as necessary to save energy. Thus, portions of the plant are temporarily not available.




Figure 64 - energy saving

1335

1333

1334

1337 Requirement:

1338 Energy saving region switch off/on shall not create process disturbance.

Communication paths through the energy saving area between end-stations, which do not belong to the energy saving area, shall be avoided.

1340 1341 1342

1343

1344

1345

1346

1347

1348

1349

1339

1336

Useful 802.1Q mechanisms:

 Appropriate path computation by sorting streams to avoid streams passing through energy saving region.

3.8.7 Use case 23: Add machine, production cell or production line

When production capacity is exhausted, additional machines, production cells or even production lines are bought and integrated into a plant.

E.g. an additional welding robot is added to a production cell to increase production capacity. The additional machine has to be integrated into the production cell control with minimal disturbance of the production cell process.

1350 1351 1352


1353

1356

Another aspect is when a machine or a group of machines is tested in a stand-alone mode first before it is used in the combination with other machines or in combination with a supervisory system.

A flexible cell communication is needed to support this. Enabling and disabling of cell communication within a machine should be possible with minimal impact on production.

Use Cases For: IEEE P802.1DG Page 67 of 79



1358 1359

1360

1361 1362

1365

1366

1367

1357

Figure 65 - add machine

Requirement:

Adding and removing a machine/cell/production line shall not disturb existing installations

<u>Useful mechanisms:</u>

1363 1364

> 3.8.8 Use case 24: Multiple applications in a station using the TSN-IA profile Technology A and B are implemented in PLC and devices.




Figure 66 - two applications

1368 1369 1370

Requirement:

Stations with multiple applications using TSN traffic classes shall be supported.

1371 1372 1373

Useful 802.1 mechanisms:

1374

Use Cases For: IEEE P802.1DG Page 68 of 79

1375 3.8.9 Use case 25: Functional safety

Functional safety is defined in IEC 61508 as "part of the overall safety relating to the EUC [Equipment Under Control] and the EUC control system that depends on the correct functioning of the E/E/PE [electrical/electronic/programmable electronic] safety-related systems and other risk reduction measures"

IEC 61784-3-3 defines a safety communication layer structure, which is performed by a standard transmission system (black channel), and an additional safety transmission protocol on top of this standard transmission system.

The standard transmission system includes the entire hardware of the transmission system and the related protocol functions (i.e. OSI layers 1, 2 and 7).

Safety applications and standard applications are sharing the same standard communication systems at the same time.




Figure 67 - Functional safety with cyclic real-time

Requirement:

Safety applications (as black channel) and standard applications share the same TSN-IA profile based communication system at the same time.

Useful 802.1 mechanisms:


1398 • .

3.8.10 Use case 26: Machine cloning

The machines used in a cell can be identical but with a different task. Robots are a typical example of that kind of machines (see Figure 68). Thus, both machines have the same internal communication flows. The difference is just different machine identification for the external flow. The concept as of today is that the machine internal configuration has its identification and the cell system has its configuration but there is no dependency between both. The machine internal setup is done earlier and the cell identification is a result from a different configuration step and is done by a different organizational unit. Thus, it is difficult to propagate the cell level identification at the very beginning to the machine internal components. A worst case scenario is the startup of a machine and the connection to a cell in an ad hoc way with identification of the machine by the globally unique MAC address of the machine and the resolution of other addresses within the cell controller or above (e.g. for allocation of IP addresses). If there is a need to communicate with a

Use Cases For: IEEE P802.1DG Page 69 of 79

1411 few field device within the machine in a global way the machine subsystem has to be configured 1412 accordingly in advance. This configuration step could be done by a different organization as the 1413 stream configuration and not all machine internal elements may require a global address.



1414 1415

1416

1417

1418

1419 1420

1422

1423

Figure 68 – Machine internal communication with isolated logical infrastructure

Requirements:

- TSN domains with unique addressing within the TSN domains;
- Unique TSN domain identification (e.g. using LLDP) also for cloned machines;
- Define handling of specific addresses (e.g. IP addresses) for global identification and how they are managed within the machine set-up procedures;

1421 Useful 802.1 mechanisms:

- IEEE 802.1Q (usage of streams)
- IEEE 802.1 support for isolation is VLAN

1424 3.9 DCS Reconfiguration

1425 3.9.1 Challenges of DCS Reconfiguration Use Cases

- 1426 The challenge these use cases bring is the influence of reconfiguration on the existing
- 1427 communication: all has to happen without disturbances to the production!
- 1428 We consider important the use case that we can connect any number of new devices wherever in 1429
- the system and they get connectivity over the existing infrastructure supporting TSN features
- 1430 without a change to the operational mode of the system.

1431

1432 3.9.2 Use case 27: DCS Device level reconfiguration

- 1433 The structure shown in **Error! Reference source not found.** applies. Figure 69 provides a logic 1434 station view.
- 1435 SW modifications to a device
- 1436 A change to the device's SW/SW application shall happen, which does not require changes to the SW/SW application running on other devices (incl. firmware update). 1437
- 1438 Device Exchange/Replacement

Use Cases For: IEEE P802.1DG Page 70 of 79

The process device is replaced by another unit for maintenance reason, e.g. for off-process calibration or because of the device being defective (note: a "defective device may still be fully and properly engaged in the network and the communication, e.g. if just the sensor is not working properly anymore).

- Use case: repair.
- Add/remove additional device(s)
 - A new device is brought to an existing system or functionality, which shall be used in the application, is added to a running device, e.g. by enabling a SW function or plugging in a new HW-module. Even though the scope of change is not limited to a single device because also the other device engaged in the same application.
 - For process devices, servers: BIOS, OS and applications updates, new VMs, workstations.
 - Use cases: replacement with upgrade/downgrade of an existing device, simply adding new devices, removal of device, adding connections between devices.
- Influencing factors relative to communication
 - Communication requirements of newly added devices (in case of adding)
 - Existing QoS parameters (i.e. protocol-specific parameters like TimeOuts or Retries)
- Device Redundancy
 - Network/Media Redundancy
 - Virtualization
 - For servers: in-premise or cloud
 - Clock types in the involved process devices
 - Universal time and working clock domains
- Cycle time(s) needed by new devices
 - Available bandwidth
- 1463 Existing security policies




Figure 69 - Device level reconfiguration use cases

3.9.3 Use case 28: DCS System level reconfiguration

The structure shown in **Error! Reference source not found.** applies. Figure 70 provides a logic station view.

- Extend an existing plant
 - Add new network segment to existing network
 - Existing non-TSN / Newly added is TSN
 - Existing TSN / Newly added is TSN
- Update the system security policy
 - [New key lengths, new security zones, new security policy]

Use Cases For: IEEE P802.1DG Page 71 of 79

1464

1443

1444

1445

1446

1447 1448

1449

1450

1451

1452

1453

1454

1455

1456

1457

1458 1459

1460

1461

1462

1465 1466

1468 1469

1467


1470

1471

1472

1473 1474

- To be defined how and by whom to be handled
 - Influencing factors
 - Same as for "device-level"



1478 1479

1480

1481

1475

1476

1477

Figure 70 - System level reconfiguration use cases

3.10 Further Industrial Automation Use Cases

3.10.1 Use case 29: Network monitoring and diagnostics

Diagnostics plays an important role in the management of systems and of devices. Industrial automation requires a method for quick reaction to failures. The error reaction shall limit the damage caused by the error and minimize the machine downtime.

The error detection shall be done within a few cycles (exact value is depending on the application) and reaction shall be specified precisely in the case of an error. Machine stop is not always the right reaction on errors. This reaction can be located at the talker and listener.

- Repairs are done by the service persons on site which have no specific communication knowledge.
- 1489 The indication of the components which have to be repaired shall occur within a few seconds.
- Machines are powered down during the repair. A typical repair time goal is below 15 min. This
- 1491 includes the restart of a machine and the indication that the problem is solved.
- Generally speaking the mechanisms used in this context are acyclic or having large cycle times so that they could perhaps be considered, from a networking perspective as sporadic. Most of the use cases related to diagnostics will be included in this category.
- 1495 Quick identification of error locations is important to minimize downtimes in production (see
 1496 also Sequence of events).
- Monitoring network performance is a means to anticipate problems so that arrangements can be planned and put into practice even before errors and downtimes occur.
- Identification of devices on an industrial Ethernet network shall be done in a common, interoperable manner for interoperability on a converged TSN network. This identification both needs to show the type of device, and the topology of the network. IEEE 802.1AB, the Link Layer Discovery Protocol (LLDP), provides one possible mechanism for this to be done at layer two, but provides a large degree of variability in implementation.

Requirement:

1504

1505

1506

1507

- Minimize downtime:
- Monitoring and diagnostics data including used TSN features shall be provided, e.g. established streams, failed streams, stream classes, bandwidth consumption, ...;

Use Cases For: IEEE P802.1DG Page 72 of 79

1508 A discovery protocol such as IEEE 802.1AB shall be leveraged to meet the needs of TSN-1509 IA; 1510 Reporting of detailed diagnostics information for TSN features shall be supported. 1511 1512 Useful 802.1 (ietf) mechanisms: 1513 MIBs (SNMP) YANG (NETCONF/RESTCONF) 1514 1515 1516 1517 3.10.2 Use case 30: Security 1518 Industrial automation equipment can become the objective of sabotage or spying. Therefore all aspects of information security can be found in industrial automation as well: 1519 1520 Confidentiality "is the property, that information is not made available or disclosed to 1521 unauthorized individuals, entities, or processes." 1522 Integrity means maintaining and assuring the accuracy and completeness of data. 1523 Availability implies that all resources and functional units are available and functioning 1524 correctly when they are needed. Availability includes protection against denial-of-service 1525 attacks. 1526 Authenticity aims at the verifiability and reliability of data sources and sinks. 1527 1528 Requirement: 1529 Optional support of confidentiality, integrity, availability and authenticity. 1530 Security shall not limit real-time communication 1531 1532 Protection against roque applications running on authenticated stations are out of scope. 1533 1534 Useful mechanisms: 1535 802.1X 1536 IEC62443 1537 1538 3.10.3 Use case 31: Firmware update Firmware update is done during normal operation to make sure that the machine e.g. with 1000 1539 1540 devices is able be updated with almost no down time. 1541 1542 With bump: separate loading (space for 2 FW versions required) and coordinated activation to 1543 minimize downtime 1544 1545 Bumpless: redundant stations with bumpless switchover – the single device may lose connection 1546 (bump) 1547 1548 Requirement: 1549 Stations shall be capable to accept and store an additional fw version without disturbance. 1550 1551 Useful 802.1 mechanisms:

Use Cases For: IEEE P802.1DG Page 73 of 79

1552

3.10.4 Use case 32: Virtualization

Workload consolidation is done by virtualizing the hardware interfaces. Even in such kind of environment the TSN features according to the TSN-IA profile shall be available and working.

vSwitch / vBridge

Figure 71 and Figure 72 show the two principle setups for an Ethernet communication concept allowing both, communication VM to Ethernet and VM to VM. The applications inside the VM shall not see, whether they communicate to another VM or an Ethernet node.




Figure 71 – Ethernet interconnect with VM based vBridge

 Figure 71 scales for an almost infinite amount of VMs, because the memory bandwidth and the compute power of the vMAC/vPort and vSwitch/vBridge VM are much higher than the PCIe bandwidth to the NIC.

Use Cases For: IEEE P802.1DG Page 74 of 79




Figure 72 - Ethernet interconnect with PCIe connected Bridge

Figure 72 fits for a limited amount of VMs, because it saves the additional vSwitch/vBridge VM. For a given amount of VMs, e.g. PCIe Gen3 x4 or Gen4 x4, seems to be sufficient.

Requirement:

vBridge and vPort should behave as real Bridge and real Port: data plane, control plane, ...

vBridge and vPort can become members of TSN domains.

Should work like use case "multiple applications"

1<u>57</u>8

Useful 802.1 mechanisms:

1580 •

3.10.5 Use case 33: Offline configuration

The configuration of a machine is typically done before the machine is actually built. This is necessary for checking the availability of all components and as input for the machine programming. This requires an electronic data sheet of the field devices. Bridging components and talker listener behavior shall be described in these files. The talker and listener parameters are deduced from the application configuration as well as the communication intervals. The bridge description may include the port properties and the amount of streams supported for the individual purposes. Performance parameters are also required to set up the system. XML based textual description is used currently to describe the capabilities of field devices used in machinery. The individual elements are combined and additional parameters are defined resulting in another file which describes a machine configuration. This file is given to the machine control unit after machine setup and used to verify the commissioning. Protocols are needed to compare the real machine elements with the configured ones. Topology discovery is an important feature as well as the access to bridges to read and write management data.

Latency requirements restrict usable topologies and vice versa. Some applications can be handled with the description of an upper bound for latency. In this case the configuration may not use the accumulated latency from the bridge description but a limit which has to be checked during setup.

Use Cases For: IEEE P802.1DG Page 75 of 79

1599 Another parameter for real time communication is the quality of time synchronization which 1600 depends upon several parameters of the components used in the synchronization path. YANG 1601 models of IEEE 802 components may be suitable for that purpose as offline database for individual bridge components and for the IEEE 802 network. It is not necessary for a machine configurator to 1602 1603 handle the YANG related protocols but use the models. YANG means a completely different 1604 language as used today and implies two databases and some transformation and consistency 1605 issues between the two descriptive units. Thus, it is recommended to provide a mapping between 1606 XML and YANG.

Requirements:

- Device type description of IEC/IEEE 60802 components containing all necessary managed objects needs to be defined
- Means to store machine configuration offline in a textual form (e.g. XML);
- Offline Online comparison of machine configuration shall be supported;

Useful 802.1 mechanisms:

IEEE 802.1 YANG models;

1614 1615

1616

1618

1619 1620

1621

1622

1623

1624

1625

1628

1631

1632

1633

1634

1635

1636

1637

1607

1608

1609

1610

1611 1612

1613

3.10.6 Use case 34: Digital twin

1617

Virtual pre-commissioning of machines can save a lot of time and money.

Up to 30 % time-saving in the development of new machines are foreseen by an increased engineering efficiency due to the implementation and usage of digital twins.

Faster development, delivery and commissioning of new machines at customer locations should be possible.

A digital twin shows the real machine in as much detail as possible and allows simulation of its operation. With the help of digital twins machines can gradually and virtually be developed – in parallel to the real production and commissioning process of the machines at customer locations.

1626 1627 <u>Requirement:</u>

Reliable planning, development, testing, simulation and optimization results shall be possible

630 <u>Useful 802.1 mechanisms:</u>

• ...

3.10.7 Use case 35: Device replacement without engineering

Any device in a plant, i.e. end-station, bridged end-station or bridge, may get broken eventually. If this happens fast and simple replacement of a broken device is necessary to keep production disturbance at a minimum (see also: 3.9.2 Use case 27: DCS Device level reconfiguration). Support of "mechanical" replacement of a failed device with a new one without any engineering effort (i.e. without the need for an engineering tool) is a prerequisite for minimal repair downtime.

1638 1639

Requirement:

In case of repair it shall be possible to replace end-stations, bridged end-stations or brides without the need of an engineering tool.

1641 1642 1643

1640

Useful 802.1 mechanisms:

1644 • ..

Use Cases For: IEEE P802.1DG Page 76 of 79

1645

Use Cases For: IEEE P802.1DG Page 77 of 79

1646		Abbreviations			
	AGV	Autonomous Guided Vehicle			
	CCTV	Closed Circuit Television			
	DCS	Distributed Control System			
	FW	Firmware			
	PA	Process Automation			
1647 1648 1649	.,.				
1650		Literature and related Contributions			
1651	<u>Literatu</u>	re:			
1652 1653 1654		per Physical Systems: Design Challenges", E. A. Lee, Technical Report No. UCB/EECS-http://www.eecs.berkeley.edu/Pubs/TechRpts/2008/EECS-2008-8.html			
1655 1656 1657	[2] Beckers, K. (2015). Pattern and Security Requirements: Engineering-Based Establishment of Security Standards; Springer; ISBN 9783319166643				
1658 1659 1660	[3] PI: Isochronous Mode – Guideline for PROFINET IO; V1.0; June 2016; available at http://www.ieee802.org/1/files/private/liaisons				
1661	Related	<u>contributions:</u>			
1662	[4] NI 1	traffic patterns for TSN: http://www.ieee802.org/1/files/public/docs2018/new-Bruckner-LNI-			
1663		atterns-for-TSN-0118.pdf			
1664					
1665 1666		ivendor Motion Control: http://ieee802.org/1/files/public/docs2018/new-industrial-enzinger-ndor-motion-control-0318-v01.pdf			
1667	manive	Table Motion Control Co To Vo 1.par			
1668		archical Domain based Network: http://www.ieee802.org/1/files/public/docs2018/60802-			
1669	<u>harima-</u>	industrial-use-case-0518-v04.pdf			
1670 1671	[7] Proc	ess Automation System Quantities: http://www.ieee802.org/1/files/public/docs2018/60802-			
1672		-system-quantities-0718-v01.pdf			
1673					
1674		Interdomain Communications: http://www.ieee802.org/1/files/public/docs2018/60802-			
1675 1676	Hantel-	TSN-Interdomain-Communications-0718.pdf			
1677 1678		e Timing Models: http://www.ieee802.org/1/files/public/docs2018/60802-enzinger-cycle-nodels-0718-v04.pdf			
1679 1680 1681 1682		chronous Drive Synchronization: http://www.ieee802.org/1/files/public/docs2018/60802-er-use-case-isochronous-drive-synchronization-0718-v01.pdf			

Use Cases For: IEEE P802.1DG Page 78 of 79

1683 [11] Machine Internal and Machine to Cell Controller (M2C) Embedded Communication: http://www.ieee802.org/1/files/public/docs2018/60802-essler-additional-use-case-0718-v01.pdf 1684 1685 1686 [12] Coexistence & Convergence in TSN-based Industrial Automation Networks: 1687 http://www.ieee802.org/1/files/public/docs2018/60802-stanica-convergence-coexistence-0718-1688 v03.pptx 1689 1690 [13] Flexible Manufacturing System (FMS) for Small Batch Customized Production: http://www.ieee802.org/1/files/public/docs2018/60802-Bai-small-batch-customized-production-1691 1692 0718-v01.pdf 1693 1694 [14] Multi-traffic transmission in industrial backbone network: 1695 http://www.ieee802.org/1/files/public/docs2018/60802-chen-multi-traffic-transmission-on-backbone-1696 0918.pdf 1697

1698

Use Cases For: IEEE P802.1DG Page 79 of 79