How to Configure Timesync for IEC/IEEE 60802?

Martin Mittelberger 11/2022 v01

General Information

Basis for Configuration

- YANG module definition for IEEE 1588 parts are defined in P1588e
- YANG module definition for IEEE 802.1AS Parts are defined in 802.1ASdn / 802.1ASdm

Selection of mandatory YANG Elements for 60802

- Nearly all elements in the YANG models are optional in the YANG model, but are specified in more detail in IEEE 1588-2019 Clause 8.2
- 60802 needs to select, which elements are required for 60802 and which ones are local matter of the applications
- Elements required for 60802 shall be listed in 60802

Configuration Datasets

1588 Model vs. 802.1AS Model

- 802.1AS
 - PTP End Instances and
 - PTP Relay Instances
- 1588
 - Ordinary Clocks
 - Boundary Clocks
 - end-to-end Transparent Clocks
 - P2P Transparent Clocks

1588 Model vs. 802.1AS Model

IEEE 802.1AS-2020 Clause 7.5.c states:

A PTP End Instance corresponds to an IEEE 1588 Ordinary Clock,

and a PTP Relay Instance is a type of IEEE 1588 Boundary Clock

... where its operation is very tightly defined, so much so that a PTP Relay Instance with Ethernet ports can be shown to be mathematically equivalent to a P2P Transparent Clock in terms of how synchronization is performed, as shown in 11.1.3.

Example: defaultDS operations conformance


(from 1588-2019 Clause 8.2.1)

Table 7—defaultDS operational conformance

Name	OC	BC	E2E TC	P2P TC
twoStepFlag	deprecated	deprecated	N/A	N/A
clockIdentity	required	required	optional ¹³	required
numberPorts	required	required	optional	required
clockQuality	required	required	N/A	N/A
priority1	required	required	N/A	N/A
priority2	required	required	N/A	N/A
domainNumber	required	required	required	required
slaveOnly	required	N/A	N/A	N/A
currentTime	management	management	management	management
instanceEnable	optional	optional	N/A	N/A
external Port Configuration Enabled	optional	optional	N/A	N/A
maxStepsRemoved	optional	optional	N/A	N/A
sdoId	required	required	required	required
instanceType	management	management	management	management

An IA-Station is either an Ordinary Clock or a Boundary Clock or both

Assumption



- A bridge component implements a P2P Relay and is configured as a Boundary Clock
- An end station component implements a PTP end instance and is configured as an Ordinary Clock
- An IA station implementing a bridge component and an end station component implements a PTP Relay and is configured as a Boundary Clock
- An IA station with multiple end stations components implements a PTP Relay and is configured as a Boundary Clock

Questions?