


NETWORK SECURITY WITH AUTOMOTIVE MACSEC. MACSEC INSIDE THE PHY.



MAC after MACsec			
Pros	Cons		
 Partitioning suggested by IEEE 802.1 	 Incompatible with PHY integration 		
 TSN algorithms act on actual frame size (Queuing after MACsec) 	■ Frame re-ordering due to scheduling (Queuing after MACsec) → dedi. SCIs		
Easy flow control btw. MAC and MACsec			
Traditional MAC timestamping			

MACsec after MAC			
Pros	Cons		
Easy to "retro-fit" into existing desings	TX-SCI mapping logic in PHY needed		
 MACsec acts on final frame ordering (re-ordering only with frame preemtion) 	 Requires special attention to make MACsec const. latency 		
	Flow control btw. MAC and MACsec		
	Poor latency due to Short-Length coding		

THE ISSUES WITH MACSEC INSIDE THE PHY. EVALUATION OF DIFFERENT FLOW CONTROL SCHEMES.

If rate at xMII is at the maximum, the rate after the MACsec block will be "above the maximum", as MACsec grows frames!

→Some kind of **flow control** is required to throttle xMII on the sending-side, otherwise every 2nd frames might be corrupted.

Mechanism	TSN Compatibility	Support	Software Impact
Accept packet loss	\bigcirc	+ +	+ +
PAUSE frames	Tx/Rx timing (itter, PHY (buffer)	Standard +	+ +
Pre-gapped IPG	Bandwidth gurantee	No Standard +	+ +
Ab-use of COL/CRS pins	Scalability, bandwdth—	Half-duplex only	+ +
Pseudo-MACsec header	+ +	- /+	+

