

# P802.1Qee – “Traffic Engineering for Bridged Networks that include Wireless Technologies” Kick-off

János Farkas

[janos.farkas@ericsson.com](mailto:janos.farkas@ericsson.com)

Editor

presented at the 2026 March IEEE 802 Plenary


2026-03-12

# *Recap: Scope*

This amendment specifies procedures and YANG data models to extend bridge attributes for traffic engineering for bridged networks that include wireless technologies whose delay variance is beyond that of point-to-point wireline MAC technologies.

# Recap: Wireless System as Logical TSN Bridge


- As per 3GPP standards, the 5G System (5GS) acts as a logical (virtual) TSN bridge



# Recap: The Challenge


- wireline and wireless have very different characteristics

**Wireline Bridge**



VS

**5GS Virtual Bridge**



- delay data from measurements: [https://github.com/DETERMINISTIC6G/deterministic6g\\_data](https://github.com/DETERMINISTIC6G/deterministic6g_data)

# Recap: Bridge Delay

- Bridge Delay [12.32.1 in IEEE Std 802.1Q-2022]

**Table 12-38—Bridge Delay attributes**


Name	Data type	Operations supported <sup>a</sup>	Conformance <sup>b</sup>	References
independentDelayMin	unsigned integer	R	B	12.32.1.1
independentDelayMax	unsigned integer	R	B	12.32.1.1
dependentDelayMin	unsigned integer	R	B	12.32.1.2
dependentDelayMax	unsigned integer	R	B	12.32.1.2

<sup>a</sup> R = Read only access; RW = Read/Write access.

<sup>b</sup> B = Required for Bridge or Bridge component support of Stream reservation remote management; b = Optional for Bridge or Bridge component support of Stream reservation remote management.

# A Solution: Extend Bridge Delay to Histogram

```
grouping delay-histogram {
  description "Delay histogram";
  leaf start {
    type uint64;
    description
      "The start value of the first bin in nano-seconds.
      If not specified, the first bin starts at 0.";
  }
  leaf bin-count {
    type uint32;
    mandatory true;
    description "Number of bins.";
  }
  list bin {
    description "Bins of histogram.";
    key index;
    leaf index {
      type uint32;
      mandatory true;
      description "The index of this bin.";
    }
    leaf width {
      type uint64;
      mandatory true;
      description "The width of this bin in nano-seconds.";
    }
    leaf count {
      type uint32;
      mandatory true;
      description "Count of values in this bin.";
    }
  }
}
```



# Recap: Bridge Delay in 802.1Q-2022

- Managed object
  - 12.32 Stream reservation remote management

This subclause specifies managed objects within the Bridge that can be used by the TSN CNC station or any other management component.

    - 12.32.1 Bridge Delay
- MIB
  - IEEE8021-TSN-REMOTE-MANAGEMENT-MIB
    - ieee8021TsnRemoteMgmtBridgeDelayTable
- YANG
  - No YANG in 802.1Q for Bridge Delay
  - However, there is YANG in IEC/IEEE 60802 for the Bridge Delay attributes

# Recap: Bridge Delay Attributes in IEC/IEEE 60802 D3.4

## 6.4.10.3.6 IEC/IEEE 60802 managed objects per bridge component

### 6.4.10.3.6.2 delayTimes

- per supported MAU Type pair and traffic class, if delayVariance is singleValue, or
- per port pair with supported MAU Types and traffic class, if delayVariance is multipleValues

#### a) independentDelayMin

The value is the minimum delay portion that is independent of frame length according to IEEE Std 802.1Q-2022, 12.32.1.1.

phy-latencies(mau-type)		
int32	mau-type;	// r
uint32	latency;	// r
uint16	latency-variation;	// r

#### b) independentDelayMax

The value is the maximum delay portion that is independent of frame length according to IEEE Std 802.1Q-2022, 12.32.1.1.

#### c) dependentDelayMin

The value is the minimum delay portion that is dependent on frame length according to IEEE Std 802.1Q-2022, 12.32.1.2.

#### d) dependentDelayMax


The value is the maximum delay portion that is dependent on frame length according to IEEE Std 802.1Q-2022, 12.32.1.2.

case multiple-values		
independend-delays-cascaded(in-port in-port-mau-type out-port out-port-mau-type traffic-class)		
uint8	in-port;	// r
int32	in-port-mau-type;	// r
uint8	out-port;	// r
int32	out-port-mau-type;	// r
tc-type	traffic-class;	// r
uint32	independent-delay-min;	// r
uint32	independent-delay-max;	// r
dependend-delays(in-port-line-speed)		
uint8	in-port;	// r
uint32	in-port-line-speed;	// r
uint8	out-port;	// r
uint32	dependent-delay-min;	// r
uint32	dependent-delay-max;	// r

**Figure 30 – Module iecieee60802-bridge**  
(imports ieee802-dot1q-bridge)

# What to do in P802.1Qee?

- Solution proposal
  - Extend Bridge Delay Min – Max values to a Histogram
- Managed object
  - Extend 12.32.1 Bridge Delay
- YANG
  - Augment ieee802-dot1q-bridge in a fashion similar to IEC/IEEE 60802?



**ERICSSON**