

Lessons from ProAV: How MILAN Shows the Path to Scalable TSN Adoption Across Markets

Dave Cavalcanti, Intel Corporation
Genio Kronauer, L-Acoustics
Marina Gutierrez, L-Acoustics



Outline

- TSN Standards & Profiles
- ProAV Requirements
- MILAN
- Deployments
- Lessons for Scaling TSN

Base TSN Standards & Profiles

- Base standards define the “tools in the TSN toolbox” with flexible protocols and capabilities
- Profiles specify required features and constraints for implementations to meet domain-specific requirements.
 - Defining strict requirements, reducing optional features and ambiguity are critical for multi-vendor system interoperability

TSN Profiles* (Examples)	IEEE 802.1BA AVB  Pro AV	IEEE 802.1DG  Automotive	IEEE/IEC 60802  Industrial	IEEE 802.1DP  Aerospace
Base TSN Standards* (Examples)	IEEE 802.1AS IEEE 802.1Qbv	IEEE 802.1Qav IEEE 802.1Qbu	IEEE 802.1Qcc/Qdj Many other tools/standards ...	

* Not a comprehensive list. Refer to <https://1.ieee802.org/tsn/> for a complete list.


Professional Audio & Video (ProAV) Converged Network and Deterministic Requirements

Networked ProAV devices are present in all kind of buildings and industrial context

- Live performances is often seen as core ProAV market, but it is just 'visible tip of the iceberg'
- Strong need for convergence with other protocols in installations

ProAV requirements:

- Working Clock and Global Time
- Guaranteed latency
- Zero congestion loss
- Well-defined resources and APIs
 - similar requirements as other applications!!!



MILAN – TSN for Professional Audio and Video

Avnu Alliance's Milan (Media-Integrated Local Area Networking) Specification builds on the IEEE 802.1BA (Audio Video Bridging Systems) TSN profile and other IEEE standards (IEEE 1722 and 1722.1) to meet ProAV requirements for media networking over Ethernet.



The Avnu Alliance maintains the Milan specification*, certifies compliant devices, and promotes interoperability based on TSN standards.

TSN
Profiles



IEEE 802.1BA-2011 – Audio Video Bridging

Base TSN
Standards

IEEE 802.1Q-2014 – Bridge and Bridged Networks

IEEE 802.1AS-2011 – Timing and Synchronization for Time Sensitive Applications

IEEE 1722-2016 – Transport Protocol for Time-Sensitive Applications in Bridged Local Area Networks

IEEE 1722.1-2021 – Device Discovery, Connection Management, and Control Protocol for IEEE 1722(TM) Based Devices

* [Milan Specification – Avnu Alliance](#) is available for free. No membership required.



MILAN



Milan TSN Capabilities

Network Synchronization & Flawless Media Playback

Accurate time synchronization (based on 802.1AS) is crucial for aligning audio streams in real time


Deterministic Data Transport & Mixed-criticality

Milan ensures predictable data delivery for AV streaming through bandwidth reservation (802.1Qat / SRP) while coexisting with best-effort traffic (802.1Qav / CBS)

Redundancy and Failover Mechanisms

Multiple network paths to provide redundancy and automatically switch to backup network paths to maintain continuous media transport





Ensuring Milan Interoperability and Plug-and-Play

Strict Interop Requirements

The Milan specification (the profile)* sets mandatory features to ensure devices from multiple manufacturers work seamlessly. The requirements include


- Media formats
- Time synchronization capabilities
- Redundancy and control plane requirements

Testing & Certification

Avnu provides open/collaborative testing opportunities (via interop events/Plugfests) and clear certification requirements that Milan device vendors must meet

* [Milan Specification – Avnu Alliance](#) is available for free. No membership required.

From Conformance to System Interoperability



Conformance vs Interoperability

Conformance alone does not guarantee system-level interoperability across different vendors and implementations.

MILAN Certification Program

MILAN pairs constrained profiles with formal testing and certification to validate protocol compliance and interoperability.

Importance of Testability

Testability and certification readiness are crucial for profiles to scale and ensure consistent implementation across vendors.

Reinforcing Standards Intent

Certification enforces consistent interpretation and implementation of standards as a technical mechanism, not just market activity.

Avnu TSN Switch Certification: Milan-AVB Switch

Profile Agnostic Testing for common features

The plan leverages the existing Avnu profile agnostic test plans for MRP, MSRP, MVRP, CBS and gPTP


ProAV Specific Testing

Additional testing based on the 802.1BA AVB profile

On track to be released Q2 2026

→ Similar programs are planned for other verticals
(Industrial/60802, Aerospace/802.1DP)

The missing piece for a fully certified Milan Network



MILAN Deployment Example: Super Bowl Halftime Show



MILAN Deployment Scale

The Super Bowl halftime show deployment exemplifies MILAN's capability in large-scale, complex live audio environments.

Network Redundancy and Reliability

The system used MILAN with tertiary AES redundancy ensuring zero tolerance for audible failure during the event.

Mission-Critical Performance

MILAN's profile-constrained IEEE 802.1 TSN system meets strict timing and mission-critical requirements in extreme conditions.

Industry Significance

Deterministic system behavior in time-critical/ failure-intolerant environments.

Source:  : Johnny Keirle https://media.licdn.com/dms/image/v2/D5610AQHOPwF79KU_iQ/image-shrink_800/B56ZxR5NsiHUAgl0/1770900380/682e-1773079200&v=beta&t=1EBfD3wLX0L-xQOhvoh-CzPqQKJkaM_H85-0071_K5U




AVB/TSN Live! Enabled by Avnu Certified Milan Devices



 <p>PROAV MILAN</p> <h3>Avicii Tribute Concert</h3> <p>Overview Avicii Tribute Concert – Meyer Sound A crowd of more than 58,000 gathered at the Avicii tribute concert at</p> <p>READ MORE »</p>	 <p>PROAV MILAN</p> <h3>GrandWest Casino</h3> <p>Overview GrandWest Casino – L-ACOUSTICS In South Africa's second-most populous city, GrandWest is home to various dining establishments, an ice</p> <p>READ MORE »</p>	 <p>PROAV MILAN</p> <h3>Ed Sheeran Mathematics Tour</h3> <p>Overview Ed Sheeran Tour – Meyer Sound More than 80,000 Irish fans burst into cheers of jubilation when the first</p> <p>READ MORE »</p>
 <p>PROAV MILAN</p> <h3>Dead & Company Tour</h3> <p>Overview Dead Company Tour – L-ACOUSTICS Dead & Company's 2022 Summer Tour, which kicked off in June at Dodge Stadium</p> <p>READ MORE »</p>	 <p>PROAV MILAN</p> <h3>Miami Ultrafest</h3> <p>Overview Miami Ultrafest – L-ACOUSTICS For more than two decades, huge crowds have gathered at Bayfront Park in downtown Miami</p> <p>READ MORE »</p>	 <p>PROAV MILAN</p> <h3>Hollywood Bowl</h3> <p>Overview Hollywood Bowl – L-ACOUSTICS Winner of 13 consecutive Pollstar Awards for Outstanding Outdoor Venue since 2004, Hollywood Bowl is</p> <p>READ MORE »</p>

Lessons for other TSN Profiles & Verticals



Application-Driven Profiles

Profiles must be explicit and application-focused, defining mandatory features for clear interoperability.

Risks of Excessive Optionality

Too many optional features reduce interoperability and increase deployment risks.


Testability and Certification Design

Profiles should be designed for testability, but test specifications and certification efforts are critical to enable verified compliance.

Ongoing Profile Refinement

Feedback from deployment should drive continuous refinement of profiles and capabilities for scalability and robustness.

Avnu testing and certification framework





Path for TSN Adoption in Industrial Automation

A Common Test Specification for the TSN Profile
One specification shared by industrial organizations




Scope

Testing covering TSN components, management and performance for Industrial devices (IA-Stations in 60802)

www.tiacc.net/

TIACC Testing strategy for IEC/IEEE 60802




Examples:

- Profile specific configuration (802.1AS Protocol settings - Table 10)
- System and time sync performance (Table 12, 13, 14)

TIACC Common Test Specification 1.0 on track for July 2026!

Steps towards 60802 device interoperability: Testing & Certification



802.1DP TSN Profile for Aerospace

The new opportunity



Required TSN Capabilities

- 1. Time Synchronization:** based on IEEE 802.1AS enables devices to operate on a unified time reference.
- 2. Traffic Shaping:** specifies the use of the credit-based shaper algorithm and enhancements for scheduled traffic.
- 3. Redundancy and Failover:** Frame Replication and Elimination (FRER) provides continuous backup mechanisms to avoid packet loss in the event of network failures.
- 4. Stream Isolation:** requires strict separation between streams to prevent faults in one device from impacting others, which is essential for handling mixed-criticality.

Avnu Alliance Certification Programs



Industry-specific Certification



Industry-specific Certifications by other organizations



Network Device Certification (Profile-based)



Pro AV

IEEE 802.1BA
Milan-AVB Switches



Industrial

60802-ready IA-Stations*




Automotive

IEEE 802.1DG
Automotive



Aerospace

802.1DP-ready Devices*



TSN Component Certification (Profile-agnostic)

IEEE 802.1AS
IEEE 802.1Qbv

IEEE 802.1Qav
IEEE 802.1Qbu ...

* Programs under development

Conclusions

- Milan shows that TSN works at scale when profiles are strict and application-driven
- Testing and Certification enable interoperable multi-vendor systems.
- The Milan approach provides a proven blueprint for scaling TSN across other verticals.
- Avnu Alliance members are applying this approach to Industrial and Aerospace verticals in collaboration with the broader industry ecosystem.