



Coherent vs Direct-Detect For 800G Client Connections

IEEE 802.3 NEA Ad Hoc
June 4th 2020
Jim Theodoras



Coherent vs Direct-Detect




Item	8 x 100G DD	4 x 200G DD	1 x 800G Coh
Transmitter			
Laser	8	4	1
Modulator	8	4	4
Mod Driver	8	4	4
DAC	8	4	4
Combiner	8:1	4:1	2:1
DSP Core	1	1	1
Receiver			
Laser	0	0	1
Photodiode	8	4	8
TIA	8	4	4
ADC	8	4	4
Splitter	1:8	1:4	2x1:4
DSP Core	1	1	1
Amount of Stuff	74	38	42




Where Does Coherent Fit?

Coherent Today



DCI

Duplex
100G-LR4, ER4, ZR4
400G-FR4, LR4



Coherent Tomorrow?

Breakout

400G-DR4 (4x100G) to DR1 Breakout

“800G-DR8” (8x100G) to DR1 Breakout?

“800G-DR4” (4x200G) to DRx Breakout?

Co-Packaged Optics